

Lloyd's Register of Shipping.

Ship's Name BRITISH SCOUT

Official No. 143979

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in MARCH, 1932.

Bridge after end bulkhead

Closing appliances are now 1 hook-bolted plate in centre.

1 hinged steel door, port side. (Nwc. May, 1933). *(new certificate issued)*

The hatch to forward pump room 23" x 23" opening 30" x .50" coaming
(P.S) in forward well is at present fitted with a steel hinged
cover .52" thick closed by means of 8 strongly constructed toggles
similar to those fitted on oil tight hatches, greased hemp joint
fitted into small channel on hatch sides and ends.

On poop deck there is at present fitted one coaling hatch (P & S)
6'0" x 36" x 30", .50" coaming with 3" x 3" x .32 rest bars
on each side. Cleats spaced 20" -24" apart. Wood covers 2½"
white pine. 2 tarpaulins, battens and wedges, all in good condition.

(Gls. Sept., 1937).

Noted
5/10/37
Lloyd's Register
Foundation

002174-002183-0098