

Lloyd's Register of Shipping.

Ship's Name "MADONNA."

Official No. —

CODE LETTERS 0U0C
GROSS TONS. 753.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in June, 1949.

Appliances for closing access openings in bulkheads at ends of detached superstructures:-

Poop. Shifting boards for full height in channels on bulkhead.

Hatches. Superstructure deck. small access hatch fitted forward of no. 2 hatchway, on centre line, giving access to nos. 1 & 2 hold tween decks, size 20" x 14" x 24" height, all .40 thickness, closed by hinged steel watertight cover, .40 thickness, with hinged bolts and butterfly nuts, operated outside.

Freeboard deck. small access hatch fitted forward of no. 2 hatchway, 3'-0" off centre line to starboard, giving access to no. 1. hold, size 23" x 23" x 10" height, all .40 thickness, fitted with 2½" thick wood cover on 2½" rest bars, 8 cleats, 1 tarpaulin, wedges and battens.

William Alcorn.

Leith.

22nd June, 1950.

Copy of this Report placed on board.

Noted.
28 JUN 1950



© 2020

Lloyd's Register
Foundation