

# Lloyd's Register of Shipping.

Ship's Name *S. S. "NEW TEXAS"*Official No. *140653*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

*A new W.T. hatch giving access to the steering gear compartment now fitted on the shelter deck to port of middle line at stem. Hatch coaming of welded construction 24" x 24" x 18" high welded to shelter deck plating. Coaming plate 7/16" thick fitted with a rubber jointed hinging W.T. steel cover capable of being operated by toggles from inside and outside the compartment.*

*Alex. M. Jenkins**Surveyor to Lloyd's Register of Shipping**LONDON. 9TH JUNE 1945.**Noted  
H.P.S.*