

5th October 1926.

Freeboard Particulars.

No. 1234.

Moulded Dimensions - 410'0" p.p. x 53'2" mld. x 31'1" mld to upper deck.

Approximate Registered Dimensions - 410.0' x 53.4' x 30.9'.

Approximate Underdeck Tonnage. - 5,190 tons.

Correction to tonnage for double bottom aft + 67 tons.

between line of longitudinals and tank top ford. + 10 tons.

Length on L.W.L. ... 409.4 feet.

Sheer ford. 8'7". Sheer  $\frac{1}{8}$  length ford. 4'9 $\frac{1}{2}$ ".

" aft. 4'8" " " aft 2'5 $\frac{1}{2}$ ".

Lowest point of sheer is at midships.

Sheers are measured on the upper deck above the midship depth.

Poop - 106'0" x 7'6" ... Closed at fore end by steel bulkhead with channel and board openings P. & S.

Bridge - 26'0" x 7'6" ... Closed at each end by steel bulkheads with channels and board opening in aft end in centre.

Forecastle - 39'0" x 7'6" - Closed at aft end by steel bulkhead.

Camber on  $\frac{1}{2}$  width ... 13 $\frac{1}{4}$ ".

*Q. M.*



© 2020

Lloyd's Register  
Foundation

002194-002205-0105