

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey

Gothenburg

Date of Survey

10-3-24

Name of Surveyor

Ship's Name

Erikssbergs Proposed S. S. for M. Dan Brostrom

Port of Registry and Nationality.

Official Number.

Gross Tonnage.

Date of Build.

Particulars of Classification.

Number in Register Book

350.0 x 50.6' x 28.0' Mtd.

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
Length on LOADLINE.		Frame Depth Rule	Ceiling Sheer	Peak Tanks
CORRECTED DIMENSIONS.	350.0			

Moulded Depth as measured

28.0

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

Addition for Keel below base line for draught record.....inches.

## CORRECTION FOR LENGTH.

Length of Ship on Loadline.....	350	
Length in Table .....	336	
Difference .....	14	
Correction for 10ft., Table A. ....	14	Table C.
× Difference divided by 10 .....	1.96	(if required.)
If $\frac{6}{10}$ ths length covered divide by 2	+2	+1"

## CORRECTION FOR IRON DECK.

Proportion covered, if less than $\frac{7}{10}$ ths length covered .....	.516.
Thickness of usual wood deck, less stringer .....	3 1/2" - 1 1/4"

## CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships.....	
Round of Beam .....	Assumed Normal
Normal round.....	
Difference .....	÷ 2 = .....
Proportion of Deck uncovered (Para. 19) .....	

NOTE.—The round of beam should be reported when the full breadth of vessel at the gunwale.

Co-efficient of fineness.....

Any modification necessary [Para. 4 (a) to (e)]\*

Co-efficient as corrected .....

Block Coeff. 80.

Say. 80

Sheer { Stem..... 102 }  
at { Sternpost ... 45 } 147 ÷ 2 = 73.5 Mean

Sheer at  $\frac{1}{2}$  of the length from { Stem }  
{ Sternpost } Assumed Gradual. Mean

Gradual mean Sheer .....

Standard mean Sheer [Table, Para. 18] ..... 45.0 Correction ✓

Difference..... 28.5 ÷ 4 = - 7 1/4

§ If limited as Para. 18 (f) .....

Rise in Sheer { At front of bridge house..... }  
from amidships { At after end of forecastle .....

Fall in Sheer { Para. 18 (d) } ÷ 2 =

Length uncovered ..... Correction

## ALLOWANCE FOR DECK ERECTIONS:—

Freeboard, Table C.....	3' 8 1/2"
Correction for Length, if required (Para. 12, 13, and 14) .....	+ 1
Freeboard by Table A. corrected for sheer, and for length, if required (Para. 12, 13, and 14) .....	6' 5 1/4"
Difference .....	2' 4 3/4"
Percentage as below.....	33.28%
	10.56

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11)

Allowance for Deck Erections

measured from Plan.

Length.	Length allowed.	Height.
Forecastle..... 35.0	35.0	8-6
Bridge House ..... 112.0 Closed		
+ Raised Qr. Dk. .... Say. 3.0 overhanging each	114.75	"
Poop..... 31.0	31.0	"
Total .....	180.75	
Length of Ship .....	350.0	
Corresponding percentage (Para. 12, 13, and 14) .....	33.28%	

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Iron) Deck:—

Fresh Water Line	above centre of Disc	...
Indian Summer Line	"	...
Winter Line	below	...
Winter North Atlantic Line	"	...

Winter Freeboard .....	5' 5 1/4"
Summer Freeboard (4-5 1/2) 4 3/4	5' 0 1/4"
Indian Summer Freeboard .....	4' 4 1/2"
N. A. Winter Freeboard .....	

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or iron deck with side.

Winter Freeboard from deck line .....	5' 6 3/4"
Summer " " " " .....	5' 2"
Indian Summer " " " " .....	4' 9 1/4"
N. A. Winter " " " " .....	
Steel Deck .....	5' 2"
	6
	4 1/2

\* If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.

† In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.

§ In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and sternpost. In vessels having poops and forecastles, it means the sheer measured at points distant one-eighth of the vessel's length from stem and sternpost.

† State dimensions of freeing port area on back of this form.

The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft, should be reported.

© 2020

Lloyd's Register Foundation

00226-00224-0058