

between Tonnage Dk. and Upper Dk.  
Total  
Gross Tonnage 8882.30

Breadth (greatest moulded) ..... B 63.0  
Depth, at middle of length from top of keel to top of beam at side of uppermost continuous deck. See Sec. 3 (1c) ..... D 35.0

Builders ROBERT DUN  
Owners UNITED M O L

COPY

For the information of Surveyors and the Committee only.

Received at Greenock Office 15th October 1929

# Lloyd's Register of Shipping.

Order: 33474/St  
Post: 4126  
Best: A 2651  
(Report on Vessel No. 19100. Port Greenock.)  
"ATHELVISCOUNT"

No. 1215 SHIP FORGINGS ~~OR CASTINGS~~

I have to report that the undermentioned ~~XXXXXX~~ Steel Forgings ~~XX~~  
~~XXXXXX~~ manufactured by Messrs. Witkowitz Bergbau & Eisenh. Gew.  
of Witkowitz for the Vessel No. 391, being built  
by Messrs. Lithgow's Ltd. of Glasgow  
for Robert Duncan & Co. Ltd.  
have been inspected by me as set forth below and found to be, so far as can  
be seen, one built up rudder without plate, sound and free from  
defects.

on Forgings ~~XXXXXX~~

Lloyd's  
No. 3523 9412/13  
HK. 8.3.29

Vienna, 9th March 1929

Hans Kolbowe

	1 rudder shaft <del>STERN FRAME</del>	1 rudder spindle <del>BRUNNEN FRAME</del>	rudder arms 1 <del>STEM</del> 1
Material*	Siemens Martin Ingot Steel	Siemens Martin Ingot Steel	Siemens Martin Ingot Steel
made	forged	forged	forged
annealed	annealed	annealed	annealed
ensions	11"Ø	12 3/8 - 9 1/2"	to sketch
ress on Inspection	almost finished	almost finished	almost finished
when Inspected	25.1; 8.3.1929	5.1; 9.2; 8.3.29	2.2; 8.3.1929
	No: 9412	No: 9413	
ts on Standard Test Pieces.			
le Test—	29.0	28.6	28.6 31.2
ons per square inch	35.5	29.6	41.5 32.9
xtension per cent. ...			
Bending Test—	180 degrees good	180 degrees good	180 degrees good
ngle before fracture			
Test—	---	---	---
ght from ground ...			
mering Test—	---	---	---
made according to Rules			
and found satisfactory ...			

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

lder arm, to sketch, Tens.str.in t/sq": 28.3 with 38.2 % elong.in 3"  
" " " 29.4 " 39.5  
" " " 29.0 " 38.2  
o l t s 3 5/8"Ø " 31.9 " 28.3E "

Bend tests good.

Fee (if any chargeable) £ : :

To be paid at VIENNA

of Iron, state whether scrap or puddled Iron. If of Steel, state whether made on the Open Hearth process.  
T.

002215-002221-0025

margin plate.....)

Spacing



Lloyd's Register  
Foundation