

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office

9 - OCT 1929

Date of writing Report 9. 11. 1929 When handed in at Local Office 7. 10. 1929 Port of GLASGOW.

No. in Survey held at GREENOCK Date, First Survey 7. 8. 29 Last Survey 11. 9. 1929
Reg. Book. (Number of Visits 7)

3931. on the M.V. ATHALYSCOUNT. Tons { Gross Not

Built at PORT GLASGOW By whom built MESSRS R. DUNCAN & CO Yard No. 391 When built 1929.

Owners MESSRS THE UNITED MOLASSES CO LTD Port belonging to LIVERPOOL.

Electric Light Installation fitted by MESSRS TELFORD GRIER & MCKAY LTD Contract No. 391 When fitted 1929.

System of Distribution Two Wire

Pressure of supply for Lighting 110 volts, Heating - volts, Power 110 volts.

Direct or Alternating Current, Lighting Direct Power Direct

If alternating current system, state frequency of periods per second -

The new installation fitted as per spec 443

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off yes

Generators, do they comply with the requirements regarding rating yes, are they compound wound yes

per spec

are they over compounded 5 per cent. yes, if not compound wound state distance between each generator -

44042

Where more than one generator is fitted are they arranged to run in parallel no, is an adjustable regulating resistance fitted in series with each shunt field yes

Are all terminals accessible, clearly marked, and furnished with sockets yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched yes

Position of Generators In main engine room near starting platform

is the ventilation in way of the generators satisfactory yes, are they clear of all inflammable material yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators - and -, are the generators protected from mechanical injury and damage from water, steam or oil yes

are their axes of rotation fore and aft yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed yes, are the prime movers and their respective generators in metallic contact yes

Main Switch Boards, where placed On bulk head near main generators.

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard -

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes yes

are they protected from mechanical injury and damage from water, steam or oil yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards - and -

are they constructed wholly of durable, non-ignitable non-absorbent materials yes, is all insulation of high dielectric strength and of permanently high insulation resistance marble slab, if semi-insulating material is used, are all conducting parts insulated from the slab

with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework yes

and is the frame effectively earthed yes. Are the fittings as per Rule regarding: - spacing or shielding of live parts yes, accessibility of all parts yes, absence of fuses on back of board yes, proportion of omnibus bars yes

individual fuses to voltmeter, pilot or earth lamp yes, connections of switches yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Double pole overload circuit breaker with time lags
Outgoing double pole change-over switches & 2 S.P. fuses

Instruments on main switchboard two ammeters two voltmeters - synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system
Switch fuse & lamp in series between each bus bar & earth

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule yes.

Cables: Single, twin, concentric, or multicore single are the cables insulated and protected as per Tables IV or V of the Rules yes

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 5V. Lighting 7V. Power

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets yes

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound yes

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage yes

Support and Protection of Cables, state how the cables are supported and protected Lead covered in steel tubing or lead covered clipped to Bulkheads in Accommodation

If cables are run in wood casings, are the casings and caps secured by screws —, are the cap screws of brass —, are the cables run in separate grooves —. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII yes

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements none

Joints in Cables, state if any, and how made, insulated, and protected none

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands yes

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed yes state the material of which the bushes are made Lead.

Earthing Connections, state what earthing connections are fitted and their respective sectional areas —, are their connections made as per Rule —

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule yes

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven none

Navigation Lamps, are these separately wired yes, controlled by separate switch and separate fuses yes, are the fuses double pole yes, are the switches and fuses grouped in a position accessible only to the officers on watch yes

has each navigation lamp an automatic indicator as per Rule yes

Secondary Batteries, are they constructed and fitted as per Rule none

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight yes, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected none

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected In W.T. wellglass fittings. In pump rooms double glass fittings, how are the cables led in W.T. screwed steel tubing

where are the controlling switches situated outside dangerous spaces.

Searchlight Lamps, No. of one, whether fixed or portable portable, are their fittings as per Rule yes

Arc Lamps, other than searchlight lamps, No. of —, are their live parts insulated from the frame or case —, are their fittings as per Rule —

Motors, are their working parts readily accessible yes, are the coils self-contained and readily removable for replacement yes

are the brushes, brush holders, terminals and lubricating arrangements as per Rule yes, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material yes

are they protected from mechanical injury and damage from water, steam or oil yes, are their axes of rotation fore and aft yes

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type none, if not of this type, state distance of the combustible material horizontally or vertically above the motors — and —

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule yes

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule yes

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings yes

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office yes

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	Two each	25	110	227	400	Enclosed steam engine	—	
AUXILIARY								
EMERGENCY								
ROTARY TRANSFORMER								

LIGHTING AND HEATING CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Ampères.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR	one	.15	37	.072	227	62	paper	L.C. & Served
	EQUALISER CONNECTIONS								
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER								
	AUXILIARY SWITCHBOARDS								
	ENGINE ROOM								
	BOILER ROOM								
	ACCOMMODATION								
	Engine Room	one	.01	7	.044	27	30	V.I.R.	L.C. & A
	Crew	one	.0145	7	.052	10	770	—	—
	Officers	one	.0225	7	.064	26	440	—	—
	Cargo	one	.01	7	.044	8	450	—	—
	Blargo	one	.01	7	.044	14	400	—	—
	Engineers	one	.01	7	.044	23	190	—	—
	Navigation	one	.007	7	.036	6	480	—	—
	Centrifuges	one	.0225	7	.064	40	90	—	—
	Workshop	one	.01	7	.044	30	90	—	—
	Steering	one	.075	19	.072	160	360	Paper	L.C. & Served
	WIRELESS	one	.01	7	.044	9	460	V.I.R.	L.C. & A
	SEARCHLIGHT	one	.04	19	.052	60	840	—	—
	MASTHEAD LIGHT								
	SIDE LIGHTS								
	COMPASS LIGHTS								
	POOP LIGHTS								
	CARGO LIGHTS								
	ARC LAMPS								
	HEATERS								

MOTOR CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Ampères.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	(A) MOTOR GENERATOR								
	(B) MAIN MOTOR								
	WORKSHOP MOTOR								
	VENTILATING FANS								

New installation fitted 4 43 (See spec 440 12)

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
 The foregoing is a correct description.

Telford, Grier & Mackay, Ltd.

Electrical Engineers.

Date 19-9-29

COMPASSES.

Distance between electric generators or motors and standard compass 200 feet.

Distance between electric generators or motors and steering compass 200

The nearest cables to the compasses are as follows:—

A cable carrying 6 Ampères 10 feet from standard compass 6 feet from steering compass.

A cable carrying 1/2 Ampères one feet from standard compass one feet from steering compass.

A cable carrying _____ Ampères _____ feet from standard compass _____ feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power Yes.

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted Yes.

The maximum deviation due to electric currents was found to be Nil degrees on any course in the case of the standard compass, and Nil degrees on any course in the case of the steering compass.

Robert Duncan
per McElly

Builder's Signature.

Date 2/10/29

Is this installation a duplicate of a previous case Yes. If so, state name of vessel Athel Duchess.

General Remarks (State quality of workmanship, opinions as to class, &c.)

This installation has been fitted on board under special survey. Tested under full working conditions and found satisfactory. The materials and workmanship were found to be good and sound.

It is submitted that this vessel is suitable for THE RECORD. Elec Light.

J.A.
10/10/29
J.P.

alg
7/10/29

Total Capacity of Generators 50. Kilowatts.

The amount of Fee ... £ 7/10.0 : When applied for, @ 5/15
 Travelling Expenses (if any) £ 10.6. : When received, 3.10.19.29

J. Rankin
 Surveyor to Lloyd's Register of Shipping.

Committee's Minute GLASGOW 8 OCT 1929

Assigned Elec Light

Im. 2. 28.—Transfer. (The Surveyors are requested not to write on or below the space for Committee's Minute.)