

Lloyd's Register of Shipping.

Ship's Name "ARDENZA".

Official No. 142025.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in _____

DEFENCE PERSONNEL ACCOMMODATION.

The aft end of No.3 Hold above the tunnel recess has been converted into accommodation for the Defence Personnel.

A companionway has been made for access to same on the port side of the raised quarter deck ^{about} shaft No.3 hatch.

This companionway is constructed of $\frac{1}{2}$ " Steel plates, size 4'-0" x 2'-6" high. Suitably stiffened. The entrance is 4'-0" x 2'-0" with $1\frac{5}{8}$ " wood door, fitted with brass lock and bolts, capable of being operated both sides. Sill 2'-0" high.

An additional W.C. has been arranged for the above on the Raised quarter Deck aft and a 4" soil pipe has been fitted through deck, discharging through ship's side, port side, and fitted with 4" storm valve.

An additional ventilator 9" dia. coaming 2'-6" high, $\frac{5}{8}$ " thick, fitted with wood plug and canvas cover now fitted on raised quarter deck aft, port side to the aforementioned accommodation.

Stockham
SURVEYOR TO LLOYD'S REGISTER.

Notel SWB

A copy has been placed on board.