

Length

165.8

Proportions—Depth—Length—Uppermost continuous deck to top of keel

TELEPHONE: LEITH 506.



Lloyd's Register of Shipping,

Royal Bank Buildings,

28, Constitution Street,

Leith, 10th October, 1931.

LLOYD'S REGISTER
RECEIVED
12 OCT 1931
LONDON

Dear Sir,

Herewith we acknowledge the receipt of your letter of the 9th instant concerning report No. 18070 on the s.s. "LAFONIA". In reply to your enquiries we may state the panting arrangements, and the strengthening of bottom forward are as approved, the floor plates in Fore Peak have been extended in height to Rule Requirements. The spacing of the riveting in the shell seams and butts, and the riveting of the butts of the upper sheerstrake and the strake below in the forward well is as approved. The writer regrets he omitted to state that rivets in seams are 4 diameters and in butts $3\frac{1}{2}$ diameters apart C. to C., and that the rivets of the butts of the upper deck sheerstrake and the strake below in the forward well are $\frac{7}{8}$ " dia.

We are, Dear Sir,

Yours faithfully,

THE SURVEYORS.

Per.

Crawford

The Secretary,

LONDON.



Lloyd's Register
Foundation

002222-002228-0009

Poop Deck, Angle, E or F

Referred to the Chief Ship Surveyor.

12 OCT 1931

Also for Mr. S. A. Hill to note.



© 2021

Lloyd's Register
Foundation