

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)
VESSELS OF 100 TONS AND UPWARDS.

G.R. 180.
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping, Signal Letters (if any) -----

Official Number.	Name of Ship.	No., Date, and Port of Registry.
161,827.	Lafonia.	9 in 1931 Leith.

No., Date, and Port of Previous Registry (if any).				
Whether British or Foreign Built.	Whether a Sailing Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steamship Single Screw	Leith	1931	Messrs. Henry Robb Ltd., Albert Road, Leith.
Number of Decks	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	Feet.	Tenths.
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	165	8
Rigged	Schooner	Main breadth to outside of plating	164	8
Stern	Elliptical	Depth in hold from tonnage deck to ceiling at midships	32	7
Build	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards	11	7.5
Galleries	None	Depth from top of beam amidships to top of keel	14	1.8
Head	Straight	Depth from top of deck at side amidships to bottom of keel	13	6.5
Framework and description of vessel	Steel cargo	Round of beam	0	7
Number of Bulkheads	5 W.T. 1 non W.T.	Length of engine room, if any	34	8
Number of water ballast tanks, and their capacity in tons	5 152 tons.			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel } 996 Tons. Ditto per inch immersion at same depth } 9.7 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
One	Direct Acting Vertical Triple Expansion, Reciprocating.	British	1931	Wm. Beardmore & Co., Glasgow.	Three	14"		90.67
	Particulars of Boilers.							700
One	Cylindrical Multitubular Steel	British	1931	MacColl & Pollock Ltd., Sunderland.	40"	27"		10 1/2 Knots
	Number of Boilers							
	Iron or Steel							
	Loaded Pressure							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck		456.92	On account of space required for propelling power		339.05
Space or spaces between Decks			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		
Turret or Trunk			These spaces are the following, viz.:-		
Forecastle		3.41	(Number of Seamen or Apprentices for whom accommodation is certified... 22.....)		61.43
Bridge space Forecastle, Side Houses in		2.04	(See Surveys 61).		
Poop or Break		151.72	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:-		
Side Houses		89.94	Master's Accommodation:		
Deck Houses			Sleeping " 3.50		
Chart House			Day " 3.50		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		53.16	Wireless " 1.95		23.91
Excess of Hatchways		10.85	Bosn's Store: Below Fore Peak Tank 4.77		
Gross Tonnage		768.04	After " " 7.18		
Deductions, as per Contra		424.39	Total		424.39
Register Tonnage		343.65			

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 140.58 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 77.01 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

- Open Forecastle - L.17.0 ft - 8.66 tons.
- Poop Overhang - L.1.8 ft - 3.92 "

Name of Master _____ Certificate of { Service No. Competency No. _____

No. of Owners _____

Name, Residence, and Description of Managing Owner if there are more owners than one.
The Falkland Islands Company Limited,
61, Gracechurch Street,
London, E.C.3.
Sixty-four (64) Shares.

Dated 28th September 1931.

