

Newcastle report

6853

Rpt. 12.

FREEBOARD VERIFICATION FORM FOR STEAMERS.

When received in London Office

WED. 13 JUN 1906

Port

Newcastle on Tyne

Vessel's Name

Cairn from now named "Odensvold"

Official No.

86733

No. in Reg. Book

69 3 sup 0

Port of Registry (For Foreign Vessels)

now "Hedevalle"

Iron or Steel

S.P.

State whether Classed by Lloyd's Register

+100A1

Name of Owners

now "J.N. Sanne"

Date of Verification

12th June 1906.

I have to report that the Freeboard from the centre of disc to the top of the statutory deck line, and the lines in connection therewith, as given below, assigned by the Committee to this vessel, have been correctly marked on the vessel's sides, in accordance with the printed instructions:—

From centre of disc to top of statutory deck line	1 ft.	6 ins. -
From centre of disc to top of statutory deck line at awning or part-awning deck	✓ 1 ft.	ins.
Fresh water line above centre of disc		4 ins. -
Indian Summer line above centre of disc		2 ins. -
Winter line below centre of disc		2 1/2 ins. -
Winter North Atlantic line below centre of disc		5 1/2 ins. -
Distance between the top of statutory deck line on vessel's side and the intersection of the continuation of upper side of wood or iron deck with the vessel's side	at main, spar or upper dk.	3/4 ins. -
	at awning or pt.-awning dk. ✓	ins.

NOTE.—It should be clearly shown whether the statutory deck line is set off from a wood or iron deck.

as assigned per Secretary's letter dated 7th April 1906. The bridge front is now stiffened with 7 x 3 x 9/20 B.S. bracketed top and bottom and spaced (average) 29" apart. with two brackets 24" x 2 1/2" fitted at rail height connecting B.H.D. with ship side. B. Claws. Surveyor.

(To be filled up in London Office.)

Statement No. 6853 Date of Committee's Minute 9.4.06

Moulded Depth for record 17 ft. 6 ins.

Freeboards compared and found correct by J.P.B. date 13.6.06

Is fee paid? Yes Form for Certificate Foreign

Instructions Write Certificate & Post. date 13 JUN. 1906

Certificate written 12-6-06 Noted for posting

