

Rpt. 13.

No. 45237

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office

62 NOV 1934

Date of writing Report 10 When handed in at Local Office 1 NOV 1934 Port of HULL

No. in Survey held at Hull Date, First Survey 16th Oct, 1934 Last Survey 25th Oct, 1934
Reg. Book. (Number of Visits 4)

on the Steel S. K " Cape Barfleur " Tons { Gross 456.92
Net 188.10

Built at Selby By whom built Cochrane & Sons Ltd. Yard No. 1127 When built 1934/10.

Owners Hudson Steam Trawling Co. Ltd. Port belonging to Hull.
Electric Light Installation fitted by Wm Broady & Son Ltd. Contract No. When fitted 1934

Is the Vessel fitted for carrying Petroleum in bulk no

System of Distribution Two wire. ✓

Pressure of supply for Lighting 100 ✓ volts, Heating ✓ volts, Power ✓ volts.

Direct or Alternating Current, Lighting Direct ✓ Power ✓

If alternating current system, state frequency of periods per second ✓

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes. ✓

Generators, do they comply with the requirements regarding rating Yes ✓, are they compound wound Yes ✓

are they over compounded 5 per cent. Yes ✓, if not compound wound state distance between each generator ✓

Where more than one generator is fitted are they arranged to run in parallel ✓, is an adjustable regulating resistance fitted in series with each shunt field ✓

Are all terminals accessible, clearly marked, and furnished with sockets Yes ✓, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched Yes ✓

Position of Generators Starboard side of engine room. ✓, are they clear of all inflammable material Yes ✓

is the ventilation in way of the generators satisfactory Yes ✓, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

and ✓, are the generators protected from mechanical injury and damage from water, steam or oil Yes ✓

are their axes of rotation fore and aft Yes ✓

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes ✓ are the prime movers and their respective generators in metallic contact Yes ✓

Main Switch Boards, where placed Beside generator in engine room

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard ✓

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes ✓

are they protected from mechanical injury and damage from water, steam or oil Yes ✓, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards. ✓ and ✓

are they constructed wholly of durable, non-ignitable non-absorbent materials Yes ✓, is all insulation of high dielectric strength and of permanently high insulation resistance Yes ✓

, if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micaite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework ✓

and is the frame effectively earthed Yes ✓. Are the fittings as per Rule regarding: — spacing or shielding of live parts

Yes ✓, accessibility of all parts Yes ✓, absence of fuses on back of board Yes ✓, proportion of omnibus bars Yes ✓

individual fuses to voltmeter, pilot or earth lamp Yes ✓, connections of switches Yes ✓

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches D.P. linked switch

for generator: outgoing circuits controlled by D.P. switches and protected by fuses on each pole.

Instruments on main switchboard One ammeters One voltmeters ✓ synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Earth lamps ✓

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules. Yes ✓

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule Yes ✓

Cables: Single, twin, concentric, or multicore twice are the cables insulated and protected as per Tables IV or V of the Rules Yes

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 1 Volt

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets Yes

Paper Insulated Cables, If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound None

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage Yes

Support and Protection of Cables, state how the cables are supported and protected L.C. cables fitted with brass clips; Armoured cables with G.I. clips.

If cables are run in wood casings, are the casings and caps secured by screws , are the cap screws of brass , are the cables run in separate grooves . If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII Yes

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements None

Joints in Cables, state if any, and how made, insulated, and protected no joints

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands Yes

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed Yes state the material of which the bushes are made Lead.

Earthing Connections, state what earthing connections are fitted and their respective sectional areas are their connections made as per Rule

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule Yes

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven None

Navigation Lamps, are these separately wired Yes, controlled by separate switch and separate fuses Yes, are the fuses double pole Yes, are the switches and fuses grouped in a position accessible only to the officers on watch Yes, has each navigation lamp an automatic indicator as per Rule no

Secondary Batteries, are they constructed and fitted as per Rule None

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight Yes, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected None, are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected None, how are the cables led None

where are the controlling switches situated

Searchlight Lamps, No. of , whether fixed or portable , are their fittings as per Rule

Arc Lamps, other than searchlight lamps, No. of , are their live parts insulated from the frame or case , are their fittings as per Rule

Motors, are their working parts readily accessible , are the coils self-contained and readily removable for replacement , are the brushes, brush holders, terminals and lubricating arrangements as per Rule , are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material , are they protected from mechanical injury and damage from water, steam or oil , are their axes of rotation fore and aft , if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type , if not of this type, state distance of the combustible material horizontally or vertically above the motors and

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN ...	One	8	100	80	350	Steam Engine.			
AUXILIARY ...									
EMERGENCY ...									
ROTARY TRANSFORMER									

DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
MAIN GENERATOR ...	1	0.06	19	0.064	160	83		V.I.R.	L.C. Armoured.
EQUALISER CONNECTIONS ...									
AUXILIARY GENERATOR ...									
EMERGENCY GENERATOR ...									
ROTARY TRANSFORMER } MOTOR GENERATOR...									
ENGINE ROOM ...	1	0.0029	3	0.036	3.5	12	20	"	"
BOILER ROOM ...	1	0.0029	3	0.036	1.5	12	40	"	"
AUXILIARY SWITCHBOARDS ...									
ACCOMMODATION ...	1	0.02214	7	0.064	12	46	150	"	"
Navigation Main	1	0.007	7	0.036	6	24	150	"	"
WIRELESS	1	0.010	7	0.044	10	31	150	"	"
SEARCHLIGHT ...	1	0.0029	3	0.036	2	12	150	"	"
MASTHEAD LIGHT ...	1	0.0029	3	0.036	2	12	30	"	L.C.
SIDE LIGHTS ...	1	0.0045	7	0.029	2	18	150	"	L.C. + armoured.
COMPASS LIGHTS ...									
POOP LIGHTS ...									
CARGO LIGHTS ...									
ARC LAMPS ...									
HEATERS ...									

DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP ...										
MAIN BILGE LINE PUMPS ...										
GENERAL SERVICE PUMP ...										
EMERGENCY BILGE PUMP ...										
SANITARY PUMP ...										
CIRC. SEA WATER PUMPS ...										
CIRC. FRESH WATER PUMPS ...										
AIR COMPRESSOR ...										
FRESH WATER PUMP ...										
ENGINE TURNING GEAR ...										
ENGINE REVERSING GEAR ...										
LUBRICATING OIL PUMPS ...										
OIL FUEL TRANSFER PUMP ...										
WINDLASS ...										
WINCHES, FORWARD ...										
WINCHES, AFT ...										
STEERING GEAR—										
(a) MOTOR GENERATOR ...										
(b) MAIN MOTOR ...										
WORKSHOP MOTOR ...										
VENTILATING FANS ...										

All Conductors are of annealed copper conforming to British Standard Specification No. 7.

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

WM BROADY & SON
ENGLISH STREET
HULL.

Electrical Engineers.

Date 23rd Oct. 1934.

COMPASSES.

Distance between electric generators or motors and standard compass 70ft

Distance between electric generators or motors and steering compass

The nearest cables to the compasses are as follows:—

A cable carrying 0.5 Ampères to feet from standard compass ✓ feet from steering compass.

A cable carrying 0.5 Ampères to feet from standard compass ✓ feet from steering compass.

A cable carrying _____ Ampères _____ feet from standard compass _____ feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted yes

The maximum deviation due to electric currents was found to be nil degrees on any course in the case of the standard

compass, and nil degrees on any course in the case of the steering compass.

FOR COCHRANE & SONS, LTD.

[Signature] DIRECTOR

Builder's Signature.

Date 25 OCT 1934

Is this installation a duplicate of a previous case yes If so, state name of vessel "Sape Nyemetyki"

General Remarks (State quality of workmanship, opinions as to class, &c.) The electrical installation of this vessel has been fitted on board under special survey, tried under working conditions and found good. It is eligible in my opinion, to have record of "Electric Light."

Noted
7/11/34
[Signature]

Total Capacity of Generators 8 Kilowatts.

The amount of Fee E.L. £ 4 : 0 : _____

When applied for, **1 NOV 1934**
When received, 9.11.34

Travelling Expenses (if any) £ _____

[Signature]
Surveyor of Lloyd's Register of Shipping.

Committee's Minute **FRI. 9 NOV 1934**

Assigned See Mchry J.E. Rpt

1m. 12.28. — Transfer. (The Surveyors are requested not to write on or below the space for Committee's Minute.)