

## Lloyd's Register of Shipping.

Ship's Name "KARABAGH."

Official No. 162683.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The steel covers on small hatchways to the Lump Room in Fore Hold, + to the Chain Locker have now been fitted with hinges, + are secured by hinged bolts + nuts.

A hatchway on poop deck has previously been fitted over the steering gear compartment, 1'-9" x 2'-0" coaming 8" x 40" with hinged steel W.T. cover secured by hinged bolts + nuts.

The coamings of the ventilators to forward + after copperdams have now been fitted with steel plate covers on screwed spindles. Covers fitted with rubber joints.

The flush scuttle on starboard side of poop has now been dispensed with, + a steel companionway built in way of same, having hinged wood door operated both sides. Door opening 4'-6" x 2'-0" sill 1'-6".

The flush scuttle on port side of poop has previously been dispensed with, to allow of fitting the companionway previously reported.

An emergency escape has been fitted in the stow plating in poop space. Opening 1'-11" x 1'-8" with hinged steel door secured by strongback, operated from within poop.

3 additional sidelights having hinged deadlights now fitted in starboard side of poop space forward.

The supports for the fore + aft gangways have now been fitted with transverse diagonal stays.

Y. Campbell

Newcastle, on - Tyne.

28<sup>th</sup> April 1943.

A copy of the above has been placed on board.

Yb.

Noted  
LWB.

17 MAY 1943

The closing appliances for the fore-castle bulkhead on the new keelboard certificates + copy has been altered as follows

Hinged (steel) doors  
wood

(this as per old certificates)

Yb.