

S.S. Nos 867-8 460.0 x 62.6 x 29.9 MLD TO U.D^K

MIDSHIP SECTION

SCALE 1/2" = 1 FT



3.6.16
14.8.16
20.9.16
29.9.16
16.10.16



PRINCIPAL DIMENSIONS

LENGTH BETWEEN PERPS	460.0
BREADTH MOULDED	62.6
DEPTH MOULDED TO UPPER D ^K	29.9
DEPTH OF HOLD	16.0

CLASS 100 A.I. LLOYDS

LOYDS NUMBERS

BREADTH MOULDED	62.6
DEPTH MOULDED TO UPPER DECK	29.25
LENGTH BETWEEN PERPS	460
PR	42435
TRANS NUMBER	12.18
LONG NUMBER	10.05

FORINGS

STERN FRAME P.P.	11.2%	R.P.	9.8%
STEM BAR	11.2%		
RUDDER AS PER RULE			

EQUIPMENT No 47229

- 2 BOWER ANCHORS 8 1/2 CWTs STOCKLESS
- 1 STREAM ANCHOR 23 1/2 CWTs EX STOCK
- 1 KEDGE
- 500 FATHOMS 2 1/2" STUD CHAIN CABLE
- 120 " 5/4" STEEL WIRE STREAM HAWSER
- 110 " 6" STEEL WIRE TOWLINE
- 20 " 16" MANILLA SPRING WITH SHACKLES
- 2 of 100 FATHOMS 8" MANILLA HAWSER & WARPS
- 2 " 8
- 4 of 100 FATHOMS 3 FLEX STEEL WIRE (PER SPEC)

Midship Section

St. Kent. Nwc rept. N^o 71177

Surrey - - - 72141

Palmerston Cas. Nos F67. 1868.



© 2020

Lloyd's Register
Foundation

002260-002268-0003