

13 MAY 1948

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "MATAROA"

Official No. 144814

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

A new steel casing built round the troop entrance ladderway between Shelter and Poop decks at N° 6 hatchway. Plating $\frac{5}{16}$ " thick stiffened with $3 \times 3 \times \frac{5}{16}$ " vertical angle stiffeners spaced 36" apart. New casing secured to top of hatch side coamings and hatchway beams at Shelter deck and to underside of hatch side coamings and hatchway beams at Poop deck. N° 6 Shelter deck hatchway covers aloft the new steel casing bolted to hatchway beams and rest bars and caulked at seams, and forward of the new steel casing additional cleats fitted, tarpaulins and battening bars altered to suit and covers securely battened down.

Cancelled

Alex. M. Jenkins & C. Little
Surveyors to Lloyd's Register of Shipping
LONDON. 31st MAY 1946.

See this reverts to the original



© 2021

Lloyd's Register
Foundation