

## Lloyd's Register of Shipping. 18 MAR 1942

Ship's Name "MATAROA"

Official No. 144814

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

ALTERATIONS:- The following alterations noted on request of Owner's representative -

COMPANIONWAYS:-

fitted on Nos 2, 5, & 6, upper deck hatchways on instructions of the Ministry of War Transport for access for forces personnel to accommodation in Nos 2, 5, & 6 'tween decks, one at each side of each of above hatches, strongly constructed of steel, secured to after end coaming & hatch beam by E.W., (hatch beams bolted in place).

Openings in companionways at Nos 2 & 5 hatchways 5'-3" x 3'-9"; sill 33" above deck.  
 " " " " No 6 " 4'-3" x 3'-9"; " " " "

Openings closed by hinged wood doors, capable of being operated from both sides & companions fitted with angles E.W. to front forming channels & 2 1/2" stormboards & tarpaulins, cleats & battens for battening down.

Suitable arrangements also made for battening down main hatches in way of companions.

Geo. Cockburn.

Glasgow 16/3/42.

(Wokingham)

Noted

19/3/42