

# Lloyd's Register of Shipping.

Ship's Name S.S. "BENRINNES" Official No. 145884

## Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

### NOW DONE:-

Port Side tween deck bunker trimming hatchway shortened and after part converted into entrance to Domestic Refrigerating Room - fitted with a strong steel companionway suitably stiffened, 6'4" long x 36" wide x 6'1" high above hatch coaming. Companionway fitted with a strong hinged steel door operated from both sides - opening 5'1" x 2'11" with 33" coaming. The size of the trimming hatchway is now 5'8" long x 36" wide. The existing entrance to the refrigerating room inside the engineers' accommodation was plated over.

*H.R. Goo*

Surveyor to Lloyd's Register of Shipping  
Philadelphia  
27th December, 1943.

*Original forwarded to owner for attachment to original Load Line Report.*

*Noted*  
3 FEB 1944  
*A.P.S.*



© 2020  
Lloyd's Register  
Foundation