

Moulded Depth

30

10 1/2"

7'-10 1/4"

- 3 1/2"

7'-6 3/4"

00274-002288-0233

FREEBOARD REPORT on the SS. "MIRANDELLA"

It is submitted the Freeboards given on the accompanying form being those required by the Tables merit approval, subject to the strongbacks (securing the portable plates in way of the openings in the bridge front) being attached to the bulkhead stiffeners by chains with riveted eyebolts, and to the freeing port area in the forward well being increased to 20 1/2 square feet on each side of the vessel.

The Surveyors should be informed that if the openings in the bridge front are closed by permanent appliances (i.e. by hinged ^{steel} doors with riveted hinges, or by plates secured in place by nut & screw bolts spaced not more than 6 inches apart and passing through both plate and bulkhead) and the freeing port area be increased as above, the freeboards may be reduced by 2 1/2 inches.

ans to return

M. H. 10/26

Draught for record

S.T.B.

18-10-26

Lloyd's Register Foundation

1 1/2"

7 3/4"

5'-2"