

BRISTOL

July 19th, 1922.

S. F. Doray

The Managing Owners Representative attend on board the  
Roumanian Steamer "EMIL GEORG V STAUSS", No. 14991 in the  
Register Book, on the 12th July 1922 and subsequent dates,  
with a view to examining both main boilers.

The port and starboard main boilers were examined  
internally and externally and several boiler tubes in all the  
back ends found choked with salt and all the furnaces distorted.

All choked tubes have been cleared and about 25 per  
cent of the tubes expanded. On account of the distortion of the  
furnaces the boiler pressure has been reduced to 180 pounds  
per square inch and the safety valves of both boilers adjusted  
to this pressure, and these boilers appear to be in a fit  
condition to enable the vessel to proceed to the Tine, where  
it is stated, they will be farther examined and repaired.

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.



*S. F. Doray*

© 2020

Lloyd's Register  
Foundation

002305-002319-0017