

# (LLOYD'S REGISTER.)

## VESSELS OF 100 TONS AND UPWARDS.

G.R. 130.  
Lloyd's Register.

*These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.*

Signal Letters (if any) **L.B.T.M.**

Official Number.	Name of Ship.	No., Date, and Port of Registry.
160,106.	St. Romanus.	20/1928 Hull.

No., Date, and Port of Previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steamship Single Screw.	Beverley.	1928.	Cook Welton & Gemmells Ltd., Beverley.

Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	Feet.	Tenths.
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	140	4
Rigged ...	Ketch	Main breadth to outside of planking floor ...	24	---
Stern ...	Elliptical	Depth in hold from tonnage deck to ceiling at midships ...	13	2
Build ...	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	---	---
Galleries ...	None	Depth from top of beam amidships to top of keel ...	14	6.2
Head ...	Straight Stem	Depth from top of deck at side amidships to bottom of keel ...	14	9
Framework and description of vessel ...	Steel trawler	Round of beam ...	0	5.8
Number of Bulkheads ...	Four	Length of engine room, if any ...	32	2.5
Number of water ballast tanks, and their capacity in tons ...	-----			

### PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ----- Tons.      Ditto per inch immersion at same depth ----- Tons.

### PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Reciprocating steam triple expansion direct acting inverted cylinders.	Engines.	Engines.	Engines.	Three	26"	-----	96 600
One	Single ended multitubular	Boilers.	Boilers.	Boilers.	13"	23"	-----	11 Knots
	Number ... One	British	1928	Chas. D. Holmes & Co. Ltd., Hull.	37"			
	Iron or Steel ... Steel							
	Loaded Pressure ... 200 lbs.							

### PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck ...		317.46	On account of space required for propelling power		177.45
Space or spaces between Decks...			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		
Turret or Trunk ...			These spaces are the following, viz.:-		
Forecastle ...			Below deck aft		11.97
Bridge space ...			(No. of seamen & apprentices for whom accommodation is certified-4)		
Pop or Break ...		17.58	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—		
Side Houses ...		1.53	Chart Space	5.96	
Deck Houses ...			Boatswains Store	7.14	
Chart House ...		5.96			13.10
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...		14.44			
Excess of Hatchways ...					
Gross Tonnage ...		356.97	Cubic Metres	1010.23	
Deductions, as per Contra ...		202.52		573.14	
Register Tonnage ...		154.45		437.09	202.52

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **86.96** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **14.44** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

**Open Forecastle, Length 19.8 feet - 11.62 Tons.**

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
<b>Thomas Hamling and Company Limited</b> St. Andrews Dock, Kingston-upon-Hull. } <b>Thomas Boyd, 531, Anlaby Road, Hull, -Manager-</b>	
Dated <b>22nd May, 1928.</b>	

