

Lloyd's Register of Shipping.

MAY 5 1939

Ship's Name *s/s "OSCAR" ex "Johan Lanne"* Official No. *5629*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in *Gothenburg 4th June, 1932. ("Johan Lanne" got. report 8845, Index No. 23849.)*

Hatchways Nos. 1, 2, 3 & 4 increased in breadth and particulars of same are now as follows:

Description of hatchway.	No. 1	No. 2	No. 3	No. 4
Dimension of "	<i>19'-2" x 15'-10³/₄"</i>	<i>21'-1" x 15'-10³/₄"</i>	<i>23'-2" x 15'-10³/₄"</i>	<i>21'-1" x 15'-10³/₄"</i>
Cramings	Stiffeners {			
	Starb. side ← <i>180 x 75 x 10⁷/₈"</i>			
	Port. side ← <i>230 x 90 x 15⁷/₈"</i>			
Stays	<i>1</i>	<i>2</i>	<i>2</i>	<i>2</i>

Hatchway beams increased in length to suit new breadth and all bottom angles of same renewed *75 x 75 x 10⁷/₈"*.

In order to suit new arrangement of the hatchway crammings the openings in the bridge front bulkhead have been reduced in breadth. The size of same is now *3'-9" x 2'-5"*.

The new gross tonnage is *1372 tons.* (British measurements)

Gothenburg 3rd May 1939.
A. Brander.