

C. Hill Room No 158.
Freeing ports.

Upper deck

$$\text{Bulkhead } 73.55 \times 3 = 220.65 \text{ sq. ft.}$$

$$\text{Area reqd by latest rules} = 14.71 \text{ sq. ft.}$$

$$\text{Area proposed } 5 @ 18" \times 24" = 15 \text{ sq. ft.}$$

$$\frac{15}{220.65} = 6.8\% \text{ of area.}$$

Quarter deck

$$\text{Bulkhead } 39.7 \times 2 = 79.4$$

$$\text{Area reqd by latest rules} = 5.25 \text{ sq. ft.}$$

$$\text{" proposed } 3 @ 1.75 \times 1.0 = 5.25 \text{ "}$$

In addition front of R.A.D.
is open.

$$\frac{5.25}{79.4} = 6.6\% \text{ of area}$$

Freeing port area approved but
recommended that ports on upper
deck be made 36" x 12".

W.H.

11.12.75



© 2020

Lloyd's Register
Foundation

002340-002351-0149