

Steel Screw Steamer, Number not given, proposed to be built by Messrs. C. Hill & Sons, Bristol, for service in the Bristol Channel, with a view to class in the Society's Register Book.

Rule dimensions : 128.75 x 20.16 x 8.75 to upper deck.
12 to raised quarter deck.

Scantling numbers : 1127 and 3722

Proportions : Length = 14.71 to upper deck.
10.73 to raised quarter deck.

Plans of midship section, profile and decks submitted by the Builders direct.

This steamer is proposed to be built with machinery aft, there being a raised quarter deck and a sunk forecastle. One very large hatchway only is proposed, the dimensions being 56'4½" x 14'. The transverse strength of the ship in way of this hatchway, however, is maintained by the fitting of three deep fixed hatch beams permanently riveted to the side coamings.


Additional strengthening to the bottom is proposed to be arranged to suit the Owners requirements, together with a slight increase in the thickness of the sheerstrake and strake below in way of the upper deck.

The scantlings and arrangements have been carefully considered and in view of the fact that there is no excess sheer forward it is considered that a full forecastle should be arranged ^{as required by the Rules} ~~be arranged~~ this affording additional protection to the hatchway mentioned above.

It is submitted that provided the hatch side coamings be additionally ^{supported} ~~strengthened~~ and ^{further} ~~additional~~ transverse ^{attachments} ~~strengthening~~ be fitted in way of the permanent hatch webs, the strengthening at the break of the raised quarter deck be amended as on the plans,

Compliance

the vessel will be worthy to be classed 100A1 "Wor service"



© 2020

Lloyd's Register
Foundation

002340-002351-0153(1/2)

(2)

in the Bristol Channel".

Loading on the Ground.

B.J.I.

see separate endorsement
for fairboard.

W. W.

W. W.
18.11.25

G. R. E.



© 2020

Lloyd's Register
Foundation

002390-002351-0153(212)

W. W.