

Lloyd's Register of Shipping.

Ship's Name "S A M A R I A"

Official No. 145923.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

ALTERATIONS:

The following single stairway openings were made in the Vessel at this time:-

Upper Promenade Deck (Frs. 97-100 (S))

Opening 8'-9" x 3'-8" with efficient compensation of doublers on deck and fore and after below.

Promenade Deck Frs. 97-100 (S)

Opening 8'-9" x 3'-8" with efficient compensation of Doublers on deck and fore and after below.

Main Deck. Frs. 97-100 (S)

Opening 8'-9" x 3'-8" with efficient compensation of Doublers on Deck and fore and after below.

Main Deck. Frs. 79-82 (S).

Opening 8'-9" x 3'-5" with efficient compensation of Doublers on deck and fore and after below.

Main Deck Frs. 59-61 (P)

Opening 8'-9" x 3'-2" with efficient compensation of Doublers on deck and fore and after below.

The above stairway openings are enclosed within boxes having doors of efficient construction and capable of being closed from both sides and having rails of adequate height

Hatch Trunkways: The following trunkways extended at this time and the trunkways to have a carrying capacity of no more than 100 cu.ft. per ton to Freeboard Deck level -

No.2 Hatch extended from 'A' to 'B' Deck.
 No.3 " " " 'A' to 'B' Deck.
 No.4 " " " 'R' to 'B' Deck.
 No.7 " " " 'R' to 'B' Deck. ✓

Additional Storm Valves.

7 W.C. Discharges 5 @ 4" dia. and 2 @ 3" diam. from 'R' Deck. *Discharges fitted with atom valves secured at all times and 4" dia. atom valves granted to First De.*
 4 Deep Tank overflow discharges 4 @ 6" diam. *above 18" above 'B' Dk. Approved by N.O.T.*
 2 Sewage Tank discharges @ 4" diam. *Discharges fitted with grained atom valves and an ordinary atom valve.*

The insulation in No.3 Lower Tween Deck deleted at this time.

The insulation in Chambers at No.1 and No.6 Holds renewed at this time.

Jas. B. Struthers
 Lloyd's Register of Shipping
 Glasgow 2/6/51
 © 1950
 Lloyd's Register
 Foundation