

HATCHWAYS ON FREEBOARD AND SUPERSTRUCTURE DECKS.									
← FREEBOARD DECK → POOP D ¹ C →									
Description of Hatchway	To Fore Peak	To Fore Hold	To Cofferdams	To Cargo Tanker	To Fore Peak	To Oil Tanker	To Prop Space	To Fore Space	To Fore Store aft.
Dimensions of Hatchway	2'0" x 2'6"	6'9" x 10'0"	6 at 23"x18"	27 at 6'0" x 4'0"	2'5" x 2'9"	2 at 3'0" x 5'0"	4 at 2'4" x 2'11"	1 at 2'8" x 2'8"	1 at 3'5" x 3'5"
COAMINGS {	Height above Deck	2½"	24" / 28½"	12 x 3½ x 3½	12" above tank	12 x 3½ x 45" B.B.	30"	30"	18"
	Thickness { Sides40	.44	x 3½ ch	12" above tank	.45 B.B.	.40	.40	.40
	Stiffeners40 ✓	.44 ✓	craming	12" above tank	.40	.40	.40 ✓	.40
	Brackets, Stays								
HATCH BEAMS {	Number	✓	✓	✓	✓	✓	✓	✓	✓
	Spacing								
	Scantling and Sketch								

Index No. 35183.

Ship's Name "ABBEYDALE"

Official No. 165409.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

in FEBRUARY, 1937.

Hatch on freeboard deck to magazine space for'd.

1 at 3'-0" x 2'-2" with 18" coaming .40" thick with hinged steel W.T. lid and 5 toggle fasteners.

Air pipes on freeboard deck to magazine space for'd.

2 - 4" dia. air pipes 2'-6" to lip with plugs and canvas covers.

Ventilators on poop deck to magazine aft

2 - 8" x 4" G.N. vents. with wood plugs and canvas covers.

NEWCASTLE - APRIL, 1938.

22 APR 1934

2-6 " " " "	36" x 30	2-0 S.O. 9-mancho to A.P. Spa co	30" x 25	<i>more covered Covered fields!</i>
1-19" Thermolite inlet.	36" x 30	2-13" S.O. mushroom vents to Pop. sp.	30" x 34	
2-6 " vents to F.O. (S.O. Type)	36" x 30	3-8" vents to Pop. accom.	30" x 30	
Freeboard 8'-4-20" vents to Pump room.	36" x 40	1-6" " to Slurry fan	3'9" x 30 supported.	
		4-12" " to Fort protein pop. sp.	30" x 34	

Particulars of Air Pipes in exposed positions on freeboard, raised quarter, or superstructure decks:—

Specialties of Air Pipes in exposed position on fireboard, raised quarter, or superstructure decks:		Ports etc.:		all air pipes closed with hinged steel covers 4 to oil fuel tanks also further with gauze	
<u>Forecastle:</u>	1-6" air pipe to F.P. tank 19" high	2-4" "	to O.F. tank 36" high		
	also has overflow in 46 shell with brass atomizer above shell deck.	2-4" "	to O.F. C.B. tank 36" "		
	1-6" air pipe to F.P. tank 2 1/2" high	2-3" "	to D.B. overflow 18" "		
	2-1/2" " " F.D. 36" high	2-3" "	to D.B. feed tank 18" "		
<u>Foreboard:</u>	2-4" " " to fore overflow 36" high	2-4" "	to A.P. tank 21" "		
	2-4" " " to aft 36" "				

Particulars of Gangway Cargo and Coaling Ports :—

None.