

Rpt. C. 11 (Contd.)

Index No. 16633

Lloyd's Register of Shipping.

Ship's Name "ELIDIR".

Official No. 113502.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

The owners have at this time dispensed with the fore and afters and Deep Beams
at the main cargo hatch and fitted 6 new beams with fore and aft wood covers.

Hatch 37' 0" x 16' 0" /

Beams 15 $\frac{1}{2}$ " x .38" thick. /

Double mounting angles top and bottom 3 $\frac{1}{2}$ " x 3" x .42" / Maximum spacing 5' 3 $\frac{1}{2}$ " /

Beaming surface 3". /

New rest bars 3 x 3 x 39. /

Wood covers 2 $\frac{3}{4}$ " thick finished. /

A horizontal stiffener has been fitted on hatch coaming p & s 8" x 3 $\frac{1}{2}$ " x .44" B.A. /

Stiffener supported by 3 plate brackets p & s, new angle hatch cleats fitted on
stiffeners spaced 24" apart. /

E. Lumsden

SURVEYOR TO LLOYD'S REGISTER.

Noted
Am.
21.1.46



© 2020

Lloyd's Register
Foundation