

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office 16 JAN 1933

Date of writing Report 2-1-1933 When handed in at Local Office 19 Port of Hamburg

No. in Survey held at Kiel Date, First Survey 21-9-32 Last Survey 3-1-33 19
Reg. Book.

62818 on the steel Twin Sc. "Geo. W. McShnight" (Number of Visits, 22)

Tons { Gross 12442
Net 7097

Built at Kiel By whom built Fr. Krupp Germania A.G. Yard No. 517 When built 1932/3

Owners Balt. Amerikanische Petr. Import Co. Port belonging to Danzig

Electric Light Installation fitted by Fried. Krupp Germania A.G. Contract No. When fitted 1932/3

Is the Vessel fitted for carrying Petroleum in bulk yes

System of Distribution two wire, two conductor system

Pressure of supply for Lighting 110 volts, Heating 110 volts, Power 110 volts.

Direct or Alternating Current, Lighting direct Power direct

If alternating current system, state frequency of periods per second

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off yes

Generators, do they comply with the requirements regarding rating yes, are they compound wound yes

are they over compounded 5 per cent. yes, if not compound wound state distance between each generator

Where more than one generator is fitted are they arranged to run in parallel no, is an adjustable regulating resistance fitted in series with each shunt field yes

Are all terminals accessible, clearly marked, and furnished with sockets yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched yes

Are the lubricating arrangements of the generators as per Rule yes

Position of Generators main engine room, lower platform, starb. side

is the ventilation in way of the generators satisfactory yes, are they clear of all inflammable material yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

and, are the generators protected from mechanical injury and damage from water, steam or oil yes

are their axes of rotation fore and aft yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed yes, are the prime movers and their respective generators in metallic contact yes

Main Switch Boards, where placed main engine room, lower platform, starb. side

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes yes

are they protected from mechanical injury and damage from water, steam or oil yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards

are they constructed wholly of durable, non-ignitable non-absorbent materials yes, is all insulation of high dielectric strength and of permanently high insulation resistance yes

if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micaite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework

and is the frame effectively earthed yes. Are the fittings as per Rule regarding:— spacing or shielding of live parts

yes, accessibility of all parts yes, absence of fuses on back of board yes, proportion of omnibus bars yes

individual fuses to voltmeter, pilot or earth lamp yes, connections of switches yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

a fuse on each pole and a double pole linked switch for each outgoing circuit:—

a fuse on each pole and a double pole change over switch


Instruments on main switchboard 2 ammeters 2 voltmeters synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

lamp alarm arrangement

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule yes



PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE	
		Kilowatts	Volts	Amps.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	2	20 each	115	175 each	375	Steam engines		
AUXILIARY	-							
EMERGENCY	-							
ROTARY TRANSFORMER	✓							

GENERATOR, LIGHTING AND HEATING CONDUCTORS.

DESCRIPTION	CONDUCTORS			COMPOSITION OF STRAND		TOTAL MAXIMUM CURRENT AMPERES		Approximate Length (Lead and Return) Feet. <i>1 1/2</i>	Insulated with	HOW PROTECTED
	No. per Pole	Total Effective Area per Pole Sq. Ins. <i>7/8</i>	No.	Diameter	In Circuit	Rule				
MAIN GENERATOR	1	120	61	1.59	175	184	6			
EQUALISER CONNECTIONS										
AUXILIARY GENERATOR										
EMERGENCY GENERATOR										
ROTARY TRANSFORMER										
ENGINE ROOM	1	2.5	1	1.75	8	18	150			
BOILER ROOM	1	2.5	1	1.75	8	18	150			
AUXILIARY SWITCHBOARDS										
Upper deck aft	1	2.5	19	1.3	40	64	80	rubber	Lead covered and armoured	
Refr. machinery	1	16	19	1.04	35	46	65			
Boilers	1	20	37	1.55	80	120	80			
Workshop	1	50	19	1.53	50	97	70			
Steering gear tele motor	1	4	19	.52	10	20	10			
ACCOMMODATION										
Bridge deck and upper deck fore	1	2.5	37	1.81	80	152	130			
Turning gear	1	3.5	19	1.53	65	80	20			
shore connections	1	120	61	1.59	200	184	18			
WIRELESS	1	10	19	.82	25	32	40			
SEARCHLIGHT	1	4	19	.52	17	20	30			
MASTHEAD LIGHT										
SIDE LIGHTS	1	2.5	19	0.3	5	18	500			
COMPASS LIGHTS										
POOP LIGHTS										
CARGO LIGHTS	1	2.5	1	1.75	9	18	130			
ARC LAMPS										
HEATERS in Galley	1	50	19	1.83	80	97	120			

MOTOR CONDUCTORS.

DESCRIPTION	No. of Motors	CONDUCTORS			COMPOSITION OF STRAND		TOTAL MAXIMUM CURRENT AMPERES		Approximate Length (Lead and Return) Feet. <i>1 1/2</i>	Insulated with	HOW PROTECTED
		No. per Pole	Total Effective Area per Pole Sq. Ins. <i>7/8</i>	No.	Diameter	In Circuit	Rule				
BALLAST PUMP											
MAIN BILGE LINE PUMPS											
GENERAL SERVICE PUMP											
EMERGENCY BILGE PUMP											
SANITARY PUMP											
CIRC. SEA WATER PUMPS											
CIRC. FRESH WATER PUMPS											
AIR COMPRESSOR											
FRESH WATER PUMP	1	1	4	19	.52	10	20	35	rubber	Lead covered and armoured	
ENGINE TURNING GEAR	2	1	3.5	19	1.53	65	80	20			
ENGINE REVERSING GEAR	1	1	2.5	1	1.75	4	18	50			
LUBRICATING OIL PUMPS											
OIL FUEL TRANSFER PUMP											
WINDLASS											
WINCHES, FORWARD											
Boiler Blowers	2	1	2.5	19	1.3	45	64	30			
WINCHES, AFT											
Fuel oil pumps for Autom. Steering Gear Flame Contr. system.	4	1	4	19	.52	6	20	30			
(a) MOTOR GENERATOR											
(b) MAIN MOTOR											
WORKSHOP MOTOR											
VENTILATING FANS											
Lathe I Lathe II	1	1	10	2.5	1	1.75	32	6	37	18	12
Shaping machine	1	1	6	19	.61	22	26	16			
Drilling	1	1	2.5	1	1.75	10	18	18			
Grinding	1	1	2.5	1	1.75	10	18	18			
Extra Compass Transformer	1	1	6	19	.61	13	26	40			
oil Purifier	1	1	2.5	1	1.75	15	18	60			

excepting small areas The German Standards have been applied generally

Cables: Single, ~~min. diameter~~ or ~~millions~~ *yes* are the cables insulated and protected as per Tables IV or V of the Rules *applied generally*

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load *3 volts*

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets *yes*

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound *none*

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *yes*

Support and Protection of Cables, state how the cables are supported and protected *armoured cables clipped. On deck armoured cables running in sheet iron troughs.*

If cables are run in wood casings, are the casings and caps secured by screws *none*, are the cap screws of brass *-*, are the cables run in separate grooves *✓*. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII *yes*

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements *yes*

Joints in Cables, state if any, and how made, insulated, and protected *gas tight joint boxes*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *yes*

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *yes* state the material of which the bushes are made *lead*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas *-*

are their connections made as per Rule *-*

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *yes*

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven *none*

Navigation Lamps, are these separately wired *yes*, controlled by separate switch and separate fuses *yes*, are the fuses double pole *yes*, are the switches and fuses grouped in a position accessible only to the officers on watch *yes*

has each navigation lamp an automatic indicator as per Rule *yes*

Secondary Batteries, are they constructed and fitted as per Rule *none*

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *yes*, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *none*

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *in cargo hose storage room cables running in tubes, switches fitted in bridge deck house.*

Lamps of the pump room fitted in gas tight pockets arranged outside in deck house where are the controlling switches situated *in bridge deck house*

Searchlight Lamps, No. of *1*, whether fixed or portable *fixed*, are their fittings as per Rule *yes*

Arc Lamps, other than searchlight lamps, No. of *-*, are their live parts insulated from the frame or case *-*, are their fittings as per Rule *-*

Motors, are their working parts readily accessible *yes*, are the coils self-contained and readily removable for replacement *yes*, are the brushes, brush holders, terminals and lubricating arrangements as per Rule *yes*, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material *yes*

are they protected from mechanical injury and damage from water, steam or oil *yes*, are their axes of rotation fore and aft *yes*, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type *✓*, if not of this type, state distance of the combustible material horizontally or vertically above the motors *-* and *-*

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule *yes*

Lighting Conductors, where lightning conductors are required, are these fitted as per Rule *none*

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *yes*

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office *yes*

All Conductors are of annealed copper conforming to British Standard Specification No. 7.

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

**FRIED. KRUPP
GERMANIA WERFT
Aktiengesellschaft**

Electrical Engineers.

Date *10/1/33*

COMPASSES.

Distance between electric generators or motors and standard compass *about 100 m*

Distance between electric generators or motors and steering compass *about 100 m*

The nearest cables to the compasses are as follows:—

A cable carrying *.5* Ampères *close to* feet from standard compass *close to* feet from steering compass.

A cable carrying *✓* Ampères *✓* feet from standard compass *✓* feet from steering compass.

A cable carrying *✓* Ampères *✓* feet from standard compass *✓* feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power *yes*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *yes*

The maximum deviation due to electric currents was found to be *nil* degrees on *✓* course in the case of the standard compass, and *nil* degrees on *✓* course in the case of the steering compass.

**FRIED. KRUPP
GERMANIA WERFT
Aktiengesellschaft**

Builder's Signature.

Date *10/1/33*

Is this installation a duplicate of a previous case *no* If so, state name of vessel *✓*

General Remarks (State quality of workmanship, opinions as to class, &c.)

*Material and workmanship of this Electric Installation are of good quality. As the conductors used are of the German Standards, the Society's Rules respecting conductors have been applied generally. The installation has been fitted in accordance with the approved plans, the Secretary's letters and in compliance with the Society's Rules. It has given satisfaction under working conditions and is eligible in my opinion for notation in the Register Book of:—
"Electric Light."*

It is submitted that this vessel is eligible for THE RECORD. Elec Light

J. A. 30/1/33

Total Capacity of Generators *40.-* Kilowatts.

The amount of Fee ... £ *25* : — : } When applied for, ... 19
Travelling Expenses (if any) £ : : } When received, ... 10.2.19.33

J. A. M. 30/1/33
Surveyor Lloyd's Register of Shipping

Committee's Minute

Assigned *Electric Light*

Im. 920.—Treasurer.
(The Surveys are requested not to write on or below the space for Committee's Minute.)



© 2020

Lloyd's Register Foundation