

SCALE :- $\frac{1}{2}$ " = ONE FOOT.

VERTICAL COUPLING 17" DEEP 16 $\frac{3}{4}$ " WIDE
2 $\frac{1}{2}$ " TH. 8 BOLTS 2 $\frac{1}{2}$ " DIAM.

DETAILS OF PINTLES AND GUDGEONS

PINTLE AT 'A' 7" DIAM 8" DEEP

B 12

H 7 1/4 18% 8

PINTLES TO BE FITTED WITH FEATHERS TO PREVENT TURNING

SEMI-CIRCULAR LOCKING PLATES ON PINTLE NUTS

5/8 LIGNUM VITAE BUSH IN ALL GUDGEONS

3/8 BRASS BUSH ON ALL PINTLES.

HARD STEEL CONICAL BEARING IN GUDGEON AT H

DETAILS OF TILLER

RADIUS 4.4×10^2 RODS 12 DIAM

BOSS ~~1/2~~ DEEP ~ 13 1/2" OUTSIDE DIAM

ARM ~~1 3/4"~~ CHAINS ~~1 3/8"~~ DIAM

JOHN TUTIN M.Sc.

37 WELDON AVENUE

SUNDERLAND

S.

Intin Balanced Rudder

Cowpen D. D. Co.

242-3.

11-10-27.

242. "Crashpool" now Scandros

243. "Crashpool" (Sunk)

Intin Rudder.

Cowpen D. D. Co.

242-3.

N/N 'ACROPOLIS'