

19 OCT 1955

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name ADELLEN Official No. 164860

Port of Registry Middlesbrough.

This ship has been under survey at North Shields.

on 22nd, 23rd, 26th Sept. & 14th Oct. 1955 and the following alterations to the conditions of assignment of loadlines have now been effected/~~to be~~:-

Now fitted 35 Butterworth Openings in Upper Deck, to main cargo tanks, each 12 1/2" dia. Compensating steel ring elect. welded to deck 20 1/4" outside dia., 3 1/2" wide & 1" thick. Openings closed by .75" thick cover plates (steel) 20 1/4" dia. secured by 12 - 7/8" steel studs spaced approx. 4 3/8" apart and with Tobin Bronze nuts.

L. Brewer

SURVEYOR TO LLOYD'S REGISTER,
NEWCASTLE-ON-TYNE.

*Noted at
25-10-55*

A

A copy of this Report has been placed on board.

