

COPY.

31st October, 1905.

Gentlemen,

With reference to Mr. French's Report No. 14464 on the new steamer "AFRICA", I am directed to point out that the figures given by him shew a discrepancy of some $3\frac{1}{2}$ " compared with the measurements furnished on the freeboard and first entry reports and the plans of the vessel, thus:-

Moulded depth	11'. 9"
Stringer plate	$\frac{1}{2}$ "
Statutory deck line correction	1"
Bar keel	7"
	<hr/>
Total depth	12'. $5\frac{1}{2}$ "
Summer freeboard assigned and reported to have been correctly marked	8"
	<hr/>
Mean draft	11'. $9\frac{1}{2}$ " corresponding to the assigned summer freeboard.

At the time of the survey the centre of disc was reported to be $2\frac{1}{2}$ " mean above water line, which should therefore correspond to $10\frac{1}{2}$ " freeboard from top of statutory deck line and to a mean draft of $11'. 7\frac{1}{2}"$, whereas the mean draft is now reported by Mr. French to be $11'. 3\frac{3}{4}"$.

I am, Gentlemen,

Your obedient servant,

The Surveyors,
GREENOCK.



© 2020
Secretary,
Lloyd's Register
Foundation

002410-002417-0049