

No. 1120.

- Freeboard Particulars -

0'-10" x 36'-10" x 24'-9" Moulded to Awning deck.

17'-2" " " Upper "

Estimated Underdeck tonnage to Awning deck - 1,690
" " " " Upper " - 1,090

Sheer Art 2'-2" ^{= 2'-0"} Sheer at $\frac{1}{8}$ length from Art $12\frac{1}{2}" = 10\frac{1}{2}"$
" Ford 5'-7" ^{= 5'-5"} " " " " Ford $3'-5\frac{1}{2}" = 3'-3\frac{1}{2}"$
Sheer Amids. 2"

Vessel is designed to have a Summer freeboard
of 4'-9" from top of Statutory deck taken at $1\frac{1}{2}"$
above $2\frac{1}{2}"$ wood deck at side of Awning deck at amidships
and scantlings are made to suit this freeboard.

Table
A



© 2020
March 1920.

Lloyd's Register
Foundation

002435-002441-0053