

Preliminary Freeboard 35806 Lloyd's Register of Shipping. SURVEYS FOR FREEBOARD.-STEAM SHIPS.

31592

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey *Hull*
Date of Survey
Name of Surveyor *Wm. Baifair*

Ship's Name. *Good S. B. & R. Co. No 265*
Port of Registry and Nationality.
Official Number.
Gross Tonnage.
Date of Build.
Particulars of Classification. *+100 A1. Cont. B. (Revised Rules)*

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
	<i>176</i>	<i>28.33 mld.</i>	<i>11.58</i>	
Length on LOADLINE.	<i>176</i>	Frame Depth <i>5 1/2</i> Rule <i>3 1/2</i>	Ceiling <i>fitted</i> Sheer <i>+47</i>	Peak Tanks
CORRECTED DIMENSIONS.	<i>176.0</i>	<i>28.17</i>	<i>12.05</i>	

Moulded Depth as measured *13.6*
Addition for Keel below base line for draught record.....inches.

NOTE. - If the depth is measured when vessel is afloat, the details of measurement should be reported.

13.6
7 1/2
14.1 1/2
2.6 1/2
11.7

CORRECTION FOR LENGTH.

Length of Ship on Loadline.....*176*
Length in Table*162*
Difference*14*
Correction for 10ft., Table A.*9* Table C.
× Difference divided by 10*1.26* (if required.)
If 1/10ths length covered divide by 2*.63* *+3/4*

CORRECTION FOR IRON DECK.

Proportion covered, if less than 1/10ths length covered
Thickness of usual wood deck, less stringer*3* *-3*

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships.....*28.4*
Round of Beam*7 1/2*
Normal round.....*7.08*
Difference*42 ÷ 2 = 21*
Proportion of Deck uncovered (Para. 19)*233*

NOTE. - The round of beam should be reported on the full breadth of vessel at the gunwale.

Co-efficient of fineness.....
Any modification necessary [Para. 4 (a) to (e)]*
Co-efficient as corrected.....
The coefficient of load displacement as supplied by Builders -.73.
Lay .74 Provisionally.

Sheer { Stem.....*54*
at { Sternpost.....*33* } *90 ÷ 2 = 45* Mean *36 16.94*
Sheer at 1/8 of the length from { Stem *31*
Sternpost *18* } *49 ÷ 2 = 24.5* Mean *47*
Gradual mean Sheer*44.54*
Standard mean Sheer [Table, Para. 18]*27.60* Correction
Difference.....*16.94 ÷ 4 = 4.24*
§ If limited as Para. 18 (f)*-4 1/4*

Rise in Sheer { At front of bridge house.....
from amidships { At after end of forecastle.....

Fall in Sheer {
Para. 18 (d) }
Length uncovered
Correction

ALLOWANCE FOR DECK ERECTIONS :-

Freeboard, Table C.....*0-5*
Correction for Length, if required (Para. 12, 13, and 14)
Freeboard by Table A, corrected for sheer, and for length, if required (Para. 12, 13, and 14)*1-8 3/4*
Difference*1-3 3/4*
Percentage as below.....*65.05%*
Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11)*+ .35*
Allowance for Deck Erections*9.89*
.....*-10.24*

	Length.	Length allowed.	Height.
Forecastle.....	<i>23</i>	<i>22.65</i>	<i>6.11"</i>
Bridge House.....	<i>11</i>	<i>11.00</i>	<i>7.2"</i>
† Raised Qr. Dk.....	<i>101.33</i>	<i>101.33</i>	<i>4.75</i>
Poop.....			
Total		<i>134.98</i>	
Length of Ship		<i>176.0</i>	
Corresponding percentage { (Para. 11, 12, 13, or 14) }	<i>65.05%</i>		

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, *Wood (Steel) Deck :-*

Fresh Water Line above centre of Disc
Indian-Summer Line
Winter Line below
Winter-North-Atlantic-Line

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the ~~wood~~ steel deck with side. *1/4*

Winter Freeboard from deck line*5-0 3/4*
Summer " " "*4-10 3/4*
Indian-Summer " " "
N.A. Winter " " "
R.Q. " " "*4-11*
.....*3*
.....*2*

13.6
4.3
1 3/4
17-10 3/4
4-11
12-11 3/4

† If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.
† In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.
§ In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and stern-post. In vessels having poops and forecastles, it means the sheer measured at points distant one-eighth of the vessel's length from stem and stern-post.

* Note these heights are taken from that shown on approved plans.

† State dimensions of freeing port area on back of this form.

‡ The Surveyor should state whether the full in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft should be reported.

Lloyd's Register
Foundation

7.2.25 002442-02448-0189

