

8 MAY 1954

Rpt. C. 11 (Contd.)

Index No. F2018

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name TSMV "BLYTH NAVIGATOR" (ex OLIVEBANK-54) Official No. 148889

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

Plan N° 14 on C11 (contd) issued at Newcastle on 23rd April 1954 now
cancelled & the following alterations now carried out:—

From Deckhouse Aft on Shelter Deck:

1-2" dia. scupper (P23) led overboard above freeboard deck & fitted with
G.M. automatic N.R. valve at ship's side.

From Poop Accommodation Aft, above freeboard deck:

1-4" dia. sanitary discharge (P23) led overboard above freeboard deck
and fitted with G.M. automatic N.R. valve at ship's side.

1-3" dia. (S) & 1-2" dia. (P) scuppers led overboard above freeboard deck
and fitted with G.M. automatic N.R. valves at ship's side.

1-3" dia. scupper (P23) led overboard below freeboard deck and fitted
with G.M. screw down N.R. valve at ship's side, controlled from above
shelter deck & fitted with open/shut indicators.

From Accommodation etc. Midships above freeboard deck:

1-4" dia. sanitary discharge (port) led overboard above freeboard deck
and fitted with G.M. screwdown N.R. valve at ship's side controlled from
above freeboard deck & fitted with open/shut indicators.

1-1½" dia. sanitary discharge (port) led overboard above freeboard
deck & fitted with G.M. automatic N.R. valve at ship's side.

1-2" dia. scupper (P23) led overboard below freeboard deck & fitted
with G.M. screwdown N.R. valve at ship's side controlled from above
shelter deck & fitted with open/shut indicators.

(Copy placed on Board)

J. Hunter, Esq.

5-5-54

Blyth.

ALL SCUPPERS ARE FROM ACCOMMODATION

IN THE TWEEN DECKS. ON FREEBOARD DECK.

D 3.67 = .068
53.75

ap. 5.67 = .105
53.75

Nature
A.M.
10-5-54