

24 APR 1954

Index No. F1995

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name T.S.M.V. "BLYTH NAVIGATOR" (EX-"OLIVEBANK"-54). Official No. 148889

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Alterations now carried out.

Frames etc., numbered in accordance with Approved Profile & Decks Plan.

- (1.) The tonnage well bulkheads abaft No. 6 hatch removed and the tonnage hatch removed and plated over at the opening. Tonnage well scuppers (P & S) removed and openings at ship's side plated over. ✓
- (2.) A new tonnage opening now cut in shelter deck between Nos. 5 & 6 hatches in accordance with Plan previously approved for T.S.M.V. "BLYTH EXPLORER" dated 5.11.53. Tonnage opening 4'-0 $\frac{1}{2}$ " x 3'-0 $\frac{1}{2}$ " sill 9" fitted in forward bulkhead of new tonnage well, closed by 3" storm boards in channels. (3) Poop front made intact.
- (4) No. 6 hatch completely trunked in between shelter deck and freeboard deck. ✓
- (5) 5" tonnage well scuppers fitted (P & S) controlled from shelter deck and fitted with open/shut indicators GM.SDNR Valves discharging below freeboard deck. ✓
- (6) 4 - trimming hatches on freeboard deck abaft No. 5 hatch removed and deck plated over. ✓
- (7) Companionway cut in shelter deck inside midship house, port side forward, for access to new crews' accommodation on upper deck, port side. Opening fitted with adequate doubling plate. Existing 1 $\frac{3}{4}$ " hardwood door, hinged, to midship house (P & S) 5'-6" x 2'-0", sill 12". 18" OBS. ✓
- (8) Companionway cut in shelter deck in midship house, fore end, for access to new refrigerator room and cold chambers now fitted on upper deck starboard side. Opening in deck fitted with adequate doubling plate. New steel hinged access door 6'-6" x 2'-0", sill 12" fitted in house end, forward. Door operated from both sides. ✓
- (9) Collision bulkhead in tween deck space removed from No. 67 frame and repositioned on No. 76 frame. 4 side scuttles (P & S) in forecastle space abaft new bulkhead removed and openings plated over. ✓
- (10) Companionway on shelter deck forward of No. 1 hatch removed and opening plated over. ✓
- (11) Poop house extended forward to frame 70 and aft to frame 79. No additional doors fitted. ✓
- (12) Additional brass side scuttles fitted in way of new tween deck accommodation. Port side 21-12", starboard side 14-12" each fitted with hinged malleable cast iron deadlight. ✓
- (13) 5 additional 9" cowled ventilators, coaming 30" x .32" fitted on shelter deck (PS) to new tween deck accommodation, also 9-12" additional cowled ventilators, coaming 30" x .34", fitted in shelter deck to new tween deck accommodation aft. Wood PLUGS & CANVAS COVERS SUPPLIED. ✓
- (14) 1 - 3" and 1 - 2" additional scuppers fitted (P & S) discharging below freeboard deck and fitted with storm valves controlled from shelter deck and fitted with open/shut indicators. Additional discharges fitted above freeboard deck: Port 1-2", 2-1 $\frac{1}{2}$ ", Starboard 3 - 2", 1 - 3". ✓
- (15) Part of shelter deck wood sheathing permanently removed. See plan attached. ✓

(COPY PLACED ON BOARD)