

Preliminary

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

 Index No. _____
 (For London Office only.)

 PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH
 GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR
 WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS
 CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey _____

Date of Survey 29-10-19

Name of Surveyor _____

Ship's Name.

Port of Registry
and Nationality.Official
Number.Gross
Tonnage.

Date of Build.

Particulars of Classification.

The Dock Yard No 757.

Number in Register Book

| REGISTERED LENGTH. | BREADTH. | DEPTH. | UNDER DECK TONNAGE. |
|----------------------------|----------|-----------------------------|------------------------|
| 333.75 | 48.00 | 22.65 | 2940 |
| Frame Depth $9\frac{1}{2}$ | | Ceiling +0.20 | Peak |
| Rule „ $5\frac{1}{2}$ | | Sheer +1.00 | Tanks |
| $4 \times 2 = 0.67$ | | $2\frac{1}{2}$ drop in Yank | |
| | | +0.10 | |
| 333.75 | 47.33 | 23.95 | 2940 |

efficient of fineness..... 78 t.

Modification necessary

[Para. 4 (a) to (e)]*

efficient as corrected..... 76

 Stem..... 108" / 54" $162 \div 2 = 81$ Mean

 at $\frac{1}{8}$ of the length from { Stem 62" / Sternpost 25 1/2" } $87\frac{1}{2} \div 2 = 43\frac{3}{4}$ Mean
dual mean Sheer $43\frac{3}{4} \div 55 = 79.5$

dard mean Sheer [Table, Para. 18] 43.37

Difference..... 36.13

limited as Para. 18 (f).....

 fall in Sheer { At front of bridge house.....
 in amidships { At after end of forecastle.....

 all in Sheer { 2" $\div 2 = 1$ "
 Para. 18 (d) {

th covered by Bridge.....

Correction ✓

ALLOWANCE FOR DECK ERECTIONS:—

| | |
|---|-----------|
| board, Table C..... | 2'-6 3/4" |
| ction for Length, if required (Para. 12, 13, and 14)..... | + 2 1/2" |
| board by Table A, corrected for sheer, and for length, { | 2-9 1/4" |
| if required (Para. 12, 13, and 14) { | 5-1 1/2" |
| rence..... | 2-4 1/4" |
| ntage as below..... | 31.582. |

 tion for R. Q. Dk. if engine and boiler openings not
 covered by bridge house (Para. 11)

nce for Deck Erections..... -9" t.

| Length. | Length allowed. | Height. |
|---|-----------------|---------|
| stle..... 30'-9" closed + 2'-0" open | 32.79 | 7'-6" |
| e House..... 98'-0" closed + 2'-0 1/2" open | 101.27 | 7'-6" |
| ed Qr. Dk..... 29'-3 1/2" closed + 3'-0" open | 30.79 | 7'-6" |
| Total..... | 164.85 | |
| of Ship..... | 333.75 | = 49.4% |
| onding percentage { | 31.582. | |
| a. 11, 12, 13, or 14 { | | |

BOARD recommended amidships from centre of Disc to top of Statutor

 Fresh Water Line above centre of
 Indian Summer Line " "
 Winter Line below "
 Winter North Atlantic Line "

 frames, skin planking, or ceiling are of unusual thickness the breadth of
 ceiling should be reported if possible.
 also obtaining an allowance for deck erections under Para. 11 where the sheer
 the height of the R.Q.D. is to be taken from the level of the top of the
 n-decked vessels the total standard mean sheer means the sheer measure
 In vessels having poops and forecastles, it means the sheer mea
 eighth of the vessel's length from stem and stern-post.

Moulded Depth as measured... 24.11. ✓

 Addition for Keel below base line
 for draught record... 2 1/4" inches.

 NOTE.—If the
 depth is measured
 when vessel is
 afloat, the details
 of measurement
 should be reported.

 26-11
 3-3
 22-8

CORRECTION FOR LENGTH.

| | |
|--|----------------------------------|
| Length of Ship on Loadline..... | 333.75 |
| Length in Table..... | 299 |
| Difference..... | 34.75 |
| Correction for 10ft., Table A..... | 1.3 |
| Table C..... | 0.7 |
| × Difference divided by 10..... | + 4 1/2" (if required.) + 2 1/2" |
| If $\frac{1}{10}$ ths length covered divide by 2 | |

CORRECTION FOR IRON DECK.

| | |
|---|------------------------------|
| Proportion covered, if less than $\frac{1}{10}$ ths length covered..... | 5/10 |
| Thickness of usual wood deck, less stringer..... | 3 1/2" $\text{Corr} 1 1/4$ " |

CORRECTION FOR ROUND OF BEAM.

| | |
|--|------------|
| Breadth at Gunwale amidships..... | 47' |
| Round of Beam..... | 12" |
| Normal round..... | 11 3/4" |
| Difference..... | $\div 2 =$ |
| Proportion of Deck uncovered (Para. 19)..... | |

 NOTE.—The
 round of beam
 should be report-
 ed on the full
 breadth of vessel
 at the gunwale.

| | |
|---|-------|
| Freeboard, Table A..... | 5'-6" |
| Correction for Sheer..... | -9 |
| Correction for Length..... | 4'-9" |
| Allowance for Deck Erections..... | +4 |
| Correction for Round of Beam..... | 5- |
| Correction for fall in Sheer (if any)..... | |
| Correction for Iron Deck (if required)..... | |
| Additions for non-compliance with provisio | |
| Para. 11 (d) and (e) ‡ | |
| Other Corrections (if any)..... | |

Winter Freeboard...

Summer Freeboard

Indian Summer F

N. A. Winter

 Correction necess
 in accorda
 intersecti


© 2020

 Lloyd's Register
 Foundation