

Rpt. 13.

No. 57800

REPORT ON ELECTRICAL EQUIPMENT.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

23 DEC '36

Received at London Office

Date of writing Report 14th Dec 1936 When handed in at Local Office 19.12.1936 Port of Glasgow.

No. in Survey held at Glasgow. Date, First Survey 24th Sept Last Survey 14th Dec 1936

Reg. Book. 87474 on the M.V. "BRITISH POWER." (Number of Visits 7)

Tons { Gross 8334 Net 4973

Built at Glasgow. By whom built Harland & Wolff Ltd Yard No. 9689. When built 1936

Owners British Tankers Co. Ltd Port belonging to London

Electric Light Installation fitted by Harland & Wolff Ltd Contract No. 9689. When fitted 1936

Is the Vessel fitted for carrying Petroleum in bulk Yes.

System of Distribution Two wire

Pressure of supply for Lighting 110 volts, Heating - volts, Power 110 volts.

Direct or Alternating Current, Lighting Direct Power Direct

If alternating current system, state frequency of periods per second -

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes

Generators, do they comply with the requirements regarding temperature rise Yes, are they compound wound Yes

are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator -

Where more than one generator is fitted are they arranged to run in parallel Yes, is an adjustable regulating resistance fitted in series with each shunt field Yes

Have certificates of test results for machines under 100 kw. been submitted and approved Yes

Have machines over 100 kw. been inspected by the Surveyors during manufacture and testing -

Are all terminals accessible, clearly marked, and furnished with sockets Yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched Yes

Are the lubricating arrangements of the generators as per Rule Yes

Position of Generators In main Engine Room, is the ventilation in way of the generators satisfactory Yes

are they clear of all inflammable material Yes if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the generators - and -

are the generators protected from mechanical injury and damage from water, steam or oil Yes, are their axes of rotation fore and aft Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes

are the prime movers and their respective generators in metallic contact Yes Main Switch Boards, where placed In Engine Room near generators.

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard -

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes

are they protected from mechanical injury and damage from water, steam or oil Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards - and -

are they constructed wholly of durable, non-ignitable non-absorbent materials Yes

is all insulation of high dielectric strength and of permanently high insulation resistance Yes

is it of an approved type Yes, if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micaite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework Swidanyo

is the non-hygroscopic insulating material of an approved type Yes

and is the frame effectively earthed Yes. Are the fittings as per Rule regarding: - spacing or shielding of live parts

Yes, accessibility of all parts Yes, absence of fuses on back of board Yes

temperature rise of omnibus bars Yes, individual fuses to voltmeter, pilot or earth lamp Yes

are moving parts of switches alive in the "off" position No

are all screws and nuts securing connections effectively locked Yes

are any fuses fitted on the live side of switches No

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches Triple pole circuit breaker (one pole equalizer) with 1/2" g.c. trips for the 2-30KW. machines. D.P. metal fuses for 8KW generator and each outgoing circuit.

Are turbine driven generators fitted with emergency trip switch as per rule - Are cupboards or compartments containing switchboards composed of fire-resisting material or lined with approved material -


Instruments on main switchboard 12 ammeters 3

voltmeters - synchronising device for paralleling purposes. For compound machines is the ammeter connected on the opposite pole to equaliser connection

Yes Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Earth Lamps. Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes

are the fusible cutouts of an approved type Yes have the reversed



current protection devices been tested under working conditions *Yes*

construction, protection, insulation, material, and position of these as per rule *Yes*

Cables: Single, twin, concentric, or multicore *Single Twin* are the cables insulated and protected as per Tables IV, V, X or XI of the Rules *Yes*

If the cables are insulated otherwise than as per Rule, are they of an approved type *—*

any point of the installation under maximum load *4.5 Volts*

If conductors are paper or varnished cambric insulated, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound *—* or waterproof insulating tape *—*

not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *Yes* Are cables in machinery spaces, galleys, laundries, bathrooms and lavatories lead covered or run in conduit *Yes*

Support and Protection of Cables, state how the cables are supported and protected *Main: L.C.A.B in galvanized tubing run on fore & aft gangway. Circuit wiring: Engine room: L.C.A.B. Accommodation L.C.B clipped to steel woodwork.*

If cables are run in wood casings, are the casings and caps secured by screws *—*, are the cap screws of brass *—*, are the cables run in separate grooves *—* If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII *Yes*

Refrigerated Chambers, are the cables and fittings in accordance with the special requirements *—*

Joints in Cables, state if any, and how made, insulated, and protected *None*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *Yes*

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *Yes* state the material of which the bushes are made *Lead*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas *Lead casing and screwing of cables bonded electrically by means of clips & bonding glands.*

are their connections made as per Rule *—*

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *Yes* **Emergency Supply,** state position and method of control of the emergency supply and how the generator is driven *—*

Navigation Lamps, are these separately wired *Yes*, controlled by separate switch and separate fuses *Yes*, are the fuses double pole *Yes* are the switches and fuses grouped in a position accessible only to the officers on watch *Yes* has each navigation lamp an automatic indicator as per Rule *Yes*

Secondary Batteries, are they constructed and fitted as per Rule *Yes*

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *Yes* are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them: if so, how are they protected *—* are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *In tops of pump rooms - Special gaslight fittings. In gaslight tubing outside of pump rooms.* where are the controlling switches situated *in accommodation.* are all fittings suitably ventilated *Yes*, are all switches and lampholders constructed wholly of non-ignitable, non-absorbent materials *Yes*

Heating and Cooking Appliances, are they constructed and fitted as per Rule *—*, are air heaters constructed and fitted as per Rule *—*

Searchlight Lamps, No. of *Connection only*, whether fixed or portable *—*, are their fittings as per Rule *—*

Arc Lamps, other than searchlight lamps, No. of *—*, are their live parts insulated from the frame or case *—*, are their fittings as per Rule *—*

Motors, are their working parts readily accessible *Yes*, are the coils self-contained and readily removable for replacement *Yes* are the brushes, brush holders, terminals and lubricating arrangements as per Rule *Yes*, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material *Yes*, are they protected from mechanical injury and damage from water, steam or oil *Yes* are their axes of rotation fore and aft *Yes when possible*, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type *Yes*, if not of this type, state distance of the combustible material horizontally or vertically above the motors *—* and *—* have machines of over 100 BHP been inspected by the Surveyors during manufacture and testing *—*

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule *Yes*

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule *Yes*

Ships carrying Oil having a Flash Point less than 150 F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *Yes* are all fuses of the fitted cartridge type *Yes* are they of an approved type *Yes* If portable lamps for use in dangerous spaces are supplied, are they of a self-contained, battery-fed type approved by the Home Office *Yes*

Spare Gear, if the vessel is for open sea service have spares been supplied as per Rule *Yes.*

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Amps.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	2	30	110	273	550	Oil Engine 1. Steam Engine	Diesel Oil	Above 150° F.
AUXILIARY	1	8	110	73	750	Steam Engine.	—	—
EMERGENCY								
ROTARY TRANSFORMER								

GENERATOR, LIGHTING AND HEATING CONDUCTORS.

DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Diameter.	Circuit.	Rule.			
MAIN GENERATOR	1	.40	61	.093	273	288	68	Rubber	L.C.A.B.
EQUALISER CONNECTIONS	1	.15	37	.072	—	152	34	"	" "
AUXILIARY GENERATOR	1	.06	19	.064	73	83	44	"	" "
EMERGENCY GENERATOR									
ROTARY TRANSFORMER									
ENGINE ROOM. } MOTOR GENERATOR. } DB No 6.	1	.0225	7	.064	40	46	80	"	" "
BOILER ROOM. } DB No 6A.	1	.0225	7	.064	40	46	80	"	" "
AUXILIARY SWITCHBOARDS									
ACCOMMODATION									
FOR MIDSHIP. SECT. BOX No 1	1	.06	19	.064	47	83	600	"	" " 2 lighting
NAVIGATION & DB No 1.	1	.0225	7	.064	19	46	420	"	" "
LIGHTING. AFT. DB No 5	1	.0145	7	.052	21	37	290	"	" "
WIRELESS	1	.0145	7	.052	20	37	730	"	" "
SEARCHLIGHT (WORKING ONLY)	1	.014	19	.052	60	64	1300	"	" "
MASTHEAD LIGHT	1	.002	3	.029	36	7.8	440	"	" "
SIDE LIGHTS	1	.002	3	.029	36	7.8	50	"	L.C.B.
COMPASS LIGHTS	1	.002	3	.029	20	7.8	30	"	" "
POOP LIGHTS									
CARGO LIGHTS									
ARC LAMPS									
HEATERS									

MOTOR CONDUCTORS.

DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP										
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP										
EMERGENCY BILGE PUMP										
SANITARY PUMP										
CIRC. SEA WATER PUMPS										
CIRC. FRESH WATER PUMPS										
AIR COMPRESSOR										
FRESH WATER PUMP	1	1	.06	19	.064	79	83	150	Rubber	L.C.A.B.
ENGINE TURNING GEAR										
ENGINE REVERSING GEAR										
LUBRICATING OIL PUMPS										
OIL FUEL TRANSFER PUMP										
WINDLASS										
WINCHES, FORWARD										
WINCHES, AFT										
STEERING GEAR—										
(a) MOTOR GENERATOR										
(b) MAIN MOTOR										
WORKSHOP MOTOR	1	1	.01	7	.044	25.5	31	130	"	" "
VENTILATING FANS										
FORCED DR. FAN.	1	1	.0225	7	.064	39	46	150	"	" "
OIL PURIFIERS. DB M1	1	1	.06	19	.064	68.8	83	80	"	" "
REFRIG. MACHINE	1	1	.04	19	.052	64	64	150	"	" "
THERMOTANK FANS DB4-F2	1	1	.06	19	.064	46.6	83	600	"	" "

All Conductors are of annealed copper conforming to British Standard Specification No. 7 (or International Electro-technical Commission Publication No. 28).

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

For HARLAND AND WOLFF, LIMITED

R. J. Allen
Govan Secretary

Electrical Engineers.

Date 18th December 1936

COMPASSES.

Distance between electric generators or motors and standard compass 40 Feet

Distance between electric generators or motors and steering compass 30 Feet

The nearest cables to the compasses are as follows:—

A cable carrying 18 Amperes LED INTO feet from standard compass LED INTO feet from steering compass.

A cable carrying 15 Amperes 15 feet from standard compass 10 feet from steering compass.

A cable carrying 20 Amperes 27 feet from standard compass 22 feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power Yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted Yes

The maximum deviation due to electric currents was found to be Nil degrees on all the course in the case of the standard compass, and Nil degrees on all the course in the case of the steering compass.

For HARLAND AND WOLFF, LIMITED

R. J. Allen
Govan Secretary

Builder's Signature.

Date 18th December 1936

Is this installation a duplicate of a previous case No If so, state name of vessel —

General Remarks (State quality of workmanship, opinions as to class, &c.)

The electrical equipment of this vessel has been fitted on board under special survey, tested under full working conditions and found satisfactory. The materials and workmanship are good.

19/12/36.

Noted
[Signature]

23/12/36

Total Capacity of Generators 68 Kilowatts.

The amount of Fee ... £ 29 : 6 : 0

When applied for, 14/12/36

Travelling Expenses (if any) £ :

When received, 18/1/36

A. Haffner
Surveyor to Lloyd's Register of Shipping.

Committee's Minute GLASGOW 22 DEC 1936

Assigned

SEE ACCOMPANYING MACHINERY REPORT.



© 2020

Lloyd's Register Foundation