

N.N. BRITISH PIPER.

654833

I.38/843.

GH.31081.S.

417/C of 27/10/45.
Job No.1196G.

IMPERIAL (4)

Messrs. Harland and Wolff, Limited,
Govan Shipbuilding Works,
GLASGOW, S.W.

to your No.1 Main Store,
Govan Shipbuilding Works, Govan.

Paid.

Job No.1196G.
O/No.417/C.

MASTS made from Steel Tube
in sections of dimensions as
detailed, swaged together at
joints when hot.

Extreme ends left open.

1 Fore Topmast x 47ft.6" long,
comprising:-

1 - 14" o.d. x 5/16" tk. x 18'9"
1 - 11.1/2" od. x 5/16" tk. x 11'6"
1 - 10.1/2" od. x 5/16" tk. x 11'0"
1 - 9.1/2" o.d. x 5/16" tk. x 11'0"
tapered to 5.1/2" o.d. as shown.

Tel.21"
Tel.18"
Tel.18"

1 Main Topmast x 48ft.6" long,
comprising:-

1 - 14" o.d. x 5/16" tk. x 19'0"
1 - 11.1/2" od. x 5/16" tk. x 11'8"
1 - 10.1/2" od. x 5/16" tk. x 11'7"
1 - 9.1/2" od. x 5/16" tk. x 11'0"
tapered to 5.1/2" o.d. as shown.

Tel.21"
Tel.18"
Tel.18"

To Lloyds tests, requirements & inspection
and their certificate supplied.

Coated internally with bituminous
solution and painted externally with
1 coat of red oxide.



002522-002528-0149

Lloyd's Register
Foundation