

DUPLICATE

DUPLICATE

1 AUG 1946

Rpt. C. 11 (Contd.)

Index No. 29651

Lloyd's Register of Shipping. MELBOURNE

Ship's Name S.S. "CITY OF DERBY"

Official No. 146175

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in _____

Bridge after bulkhead.

The opening on starboard side, which was closed with a riveted plate at Hull, England, in October 1942 now re-opened and fitted with a portable steel plate, $\frac{3}{8}$ " thick, secured by $\frac{1}{2}$ " steel studs. The original angles for stormboards retained at opening..

Two torpedo vents removed and welded plates fitted to bulkhead in way.

A companionway on bridge deck abaft the deeptank hatchway removed and the opening in deck plating closed with a $\frac{1}{2}$ " plate over one frame space, riveted and welded.

Two sanitary discharges from bridge 'tween deck blanked off by small welded plates on outside of shell plating.

MELBOURNE, 24th May, 1946.

P. A. McIntyre
Surveyor to Lloyd's Register.

W. Steel
J. B. D.
2 AUG 1946