

Lloyd's Register of Shipping.

Ship's Name

"GAUSDAL"

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in October 1931.

18 Trimming hatches now fitted on Deckboard Deck
each 2'-6" x 2'-6" - 9x3" L coaming and fitted with
wood covers and 1 tarpaulin and clips for securing
same - no cleats.

A.R. Gibbs.

The foreing port openings 2'-6" x 2'-6" in the tannage well, as shown in
sketch, page 4, of the original Rpt C11, have been permanently closed
by riveted plates. Overboard scuppers not less than 5" in diameter
now fitted and closed with non-return valves controlled from
shelter deck

See Memo C11(a) 30.4.46
and Memo letter 11.5.46

A.R.