

February 10, 1939.

Office Copy

S.S. "BARRIE"

The minimum legal freeboard for this ship is 2'8 $\frac{1}{2}$ " with a corresponding intermediate line of 3'1" and a winter line of 3'5", but due to scantlings the freeboard to centre of diamond should not be less than 3'7 $\frac{1}{2}$ ".

An all seasons freeboard of 3'7 $\frac{1}{2}$ " has therefore been assigned.

Hatch beams to be reinforced. ✓

Doors aft to be plated over or cover fitted to open stairway. ✓

Closing arrangements for ventilators to be provided where necessary.

Closing arrangements for air pipes to be provided where necessary.

Lifelines to be fitted. ✕



© 2020

Lloyd's Register
Foundation

002568-002576-0080