

YARD No. 5

**DIMENSIONS - 190'-0" B. P. x 30'-0" x 14'-6" MLD.**

RAISED QUARTER DECK.

SCALE:-  $\frac{1}{2}$  = 1 FOOT.

<u>LYOYDS</u>	<u>NUMERALS</u>
<u>B</u>	<u>30.0</u>
<u>D</u>	<u>14.5</u>
<u>B+D</u>	<u>44.5 = TRANSVERSE NO</u>
<u>L</u>	<u>190.0</u>
<u>L x (B+D)</u>	<u>8455.0 = LONGIT<sup>UD</sup> NO</u>
<u>d</u>	<u>11.92 MAIN DECK</u>
<u>d</u>	<u>15.92 R.Q.D.</u>

PROPORTIONS

$\frac{L}{D}$	15.1	MAIN DECK.
$\frac{L}{D}$	10.27	R.Q.D.

### EQUIPMENT.

RAISED QUARTER DECK.	$120 \times 4$	480.00
BRIDGE DECK.	$12.83 \times 7.5 \times 75$	69.76
FORECASTLE DECK	$26.3 \times 7.5 \times 75$	148.00
CASINGS.	$51 \times 7.5 \times 5$	191.25
2ND. N <sup>o</sup>		8455.0

EQUIPMENT № 9344-01 (LETTER k)

3	BOWER	ANCHORS	(STOCKLESS)	5 1/4	CWTS. COLLECTIVE
1	STREAM	"	EX. STOCK.	5 1/4	"
1	KEDGE	"	"	2 1/2	"
210	FATHOMS.	1 1/2	STUD LINK CHAIN	CABLE	"
90	"	3'	STEEL WIRE	TOW LINE.	"
90	"	6'	HAND	"	"
60	"	1 1/2	STUD LINK CHAIN OR	3/4	STEEL WIRE.
90	"	5	WARD	"	"

FORECASTLE DECK

STRINGER PLATE 17' x 26 D.R. BUTTS.  
TIE PLATING 26 DECK 22" PINE.  
STRINGER ANGLE 3' x 3' x 26.  
SIDE PLATING 26 D.R. BUTTS.  
BEAM KNEES 12' x 30

SECTION THRO' MACHINERY SPACE. — (LOOKING AFT.)



94  
34

60

80  
22  
110

(12)

british

n/n "FOAMVITE"


Algeiba

64

St. Funnelstone

Appledore 32bs.

Handship. See



© 2021

Lloyd's Register  
Foundation

002602-002610-0221