

(1)

"Canberra"

Sidescuttles

(A) 14" opening type below bulkhead deck

Item	Actual	B.S.S. (1947)	
Frame & fastenings	$\frac{7}{16}$ " : not given	$\frac{1}{2}$ " : 15 $\frac{5}{8}$ "	✓
Glass thickness	1"	$1\frac{1}{8}$ "	✓
Glassholder bolts	2 $\frac{3}{4}$ " (sealed)	3 $\frac{7}{8}$ "	✓
Deadlight & bolts	<u>not fitted</u>	$\frac{3}{8}$: 3 $\frac{7}{8}$ "	✓
Bolt pins	$\frac{5}{8}$ " (sealed)	$\frac{9}{16}$ "	✓
Locking nuts	<u>No</u>	Yes	✓
Glassholder & D.L. hinge pins	$\frac{3}{8}$ " (sealed)	$\frac{3}{4}$ "	✓
Log thickness glassholder	$\frac{1}{4}$ " (sealed)	$\frac{7}{8}$ "	✓
" " Deadlight	✓	$1\frac{1}{8}$ "	✓
Plug.	$\frac{3}{8}$ "	not required : $\frac{3}{8}$ "	✓

(A₁) 11 $\frac{3}{4}$ " opening type below bulkhead deck

Item	Actual	B.S.S. (for 12")	
Frame & fastenings	$\frac{7}{16}$ " : not given	$\frac{1}{2}$ " : 13 $\frac{5}{8}$ "	✓
Glass thickness	1"	1"	✓
Glassholder bolts	2 $\frac{3}{4}$ " (sealed)	2 $\frac{7}{8}$ "	✓
Deadlight & bolts	<u>not fitted</u>	$\frac{3}{8}$: 2 $\frac{7}{8}$ "	✓
Bolt pins	$\frac{5}{8}$ " (sealed)	$\frac{9}{16}$ "	✓
Locking nuts	<u>No</u>	Yes	✓
Glassholder & D.L. hinge pins	$\frac{3}{8}$ " (sealed)	$\frac{5}{8}$ "	✓
Log thickness, glassholder	$\frac{1}{4}$ " (sealed)	$\frac{3}{4}$ "	✓
" " deadlight	✓	$1\frac{1}{8}$ "	✓
Plug	$\frac{3}{8}$ "	not required : $\frac{1}{4}$ "	✓



© 2020

Lloyd's Register
Foundation

002611-002619-002614

(B)

Canberra: Sidemuttles (contd)

(2)

12 1/2" opening type below bulkhead deck

Item	Actual	B.S.S. (12")	
Frame & fastening	9/16": not given	1/2": 13 2 5/8	✓
Glass thickness	1"	1"	✓
Glassholder bolts	3 2 3/4" (ruled)	2 2 7/8"	✓
Deadlight & bolts	5/16": 2 2 3/4" (ruled)	3/8": 2 2 7/8"	✓
Bolt pins	5/8" (ruled)	9/16	✓
Locking nuts	No	Yes	✓
Glass holder & D.L. hinge pins	5/8" (ruled)	5/8"	✓
Aug thickness: glassholder	> 1" (ruled)	3/4"	✓
" " : Deadlight	5/8" (ruled)	1 1/8"	✓

~~Plating~~

(F)

12" opening type below bulkhead deck { ~~all found~~
~~of 1/8"~~

Frame & fastening	9/16" (ruled): not given	1/2": 13 2 5/8"	✓
Glass thickness	1"	1"	✓
Glassholder bolts	2 2 3/4"	2 2 7/8"	✓
Deadlight & bolts	3/8": 1 2 3/4	3/8": 2 2 7/8"	✓
Bolt pins	9/16" (ruled)	9/16"	✓
Locking nuts	No	Yes	✓
Glassholder & D.L. hinge pins	9/16" (ruled)	5/8"	✓
Aug thickness (glassholder)	7/16" (ruled)	3/4"	✓
" " : deadlight	1/16" (ruled)	1 1/8"	✓


X (F)

12 1/2" opening type above bulkhead deck

(12")

Frame & fastening	9/16" (ruled): not given	3/8": 12 2 5/8	✓
Glass thickness	1"	1"	✓
Glassholder bolts	2 2 3/4"	2 2 3/4	✓
Deadlight & bolts	3/8": 1 2 3/4	5/16": 1 2 3/4	✓
Bolt pins	9/16" (ruled)	1/2"	✓
Locking nuts	No	No	✓
Glassholder & D.L. hinge pins	9/16" (ruled)	5/8	✓
Aug thickness: glassholder	7/16" (ruled)	3/4"	✓
" " : deadlight	1/16" (ruled)	7/8"	✓

X all found of 1/8 L.



© 2020

Lloyd's Register
Foundation00263
4

(E)

"Canberra": Sidemounts (contd)

(3)

14" opening type above bulkhead deck
(16" forward of 1/8" L)

Item	Actual	BSS
Frame & fastenings	1/2": not given	7/16": 14 2 5/8" ✓
Glass thickness	1"	1" ✓
Glassholder bolts	2 2 3/4	2 2 7/8" ✓
Deadlight & bolts	not fitted	5/16": 2 2 7/8" ✓
Bolt pins	9/16" (sealed)	9/16" ✓
Glassholder & DL hinge pins	7/16" (sealed)	5/8" ✓
Lug thickness: glassholder	3/8" (sealed)	7/8" ✓
" " : deadlight	✓	1" ✓
Plug	X not fitted.	not required: 3/8" ✓

(C)

18" opening type above bulkhead deck (16")

Frame & fastenings	11/16": not given	7/16": 16 2 5/8" ✓
Glass thickness	1 1/4	1 1/8" ✓
Glassholder bolts	3 2 1"	3 2 1" ✓
Deadlight & bolts	not fitted	5/16": 2 2 1" ✓
Bolt pins	1/2" (sealed)	5/8" ✓
Glassholder & DL hinge pins	5/8" (sealed)	5/8" ✓
Lug thickness (glassholder)	1 3/4"	1" ✓
" " (Deadlight)	✓	1 1/8" ✓
Plug	not fitted	not required: 3/8" ✓

(B)

12 1/2" opening type above bulkhead deck 12"

Frame & fastenings	9/16": not given	3/8": 12 2 5/8" ✓
Glass thickness	1"	1" ✓
Glassholder bolts	3 2 3/4" (sealed)	2 2 3/4" ✓
Deadlight & bolts	5/16": 2 2 3/4" (sealed)	5/16": 1 2 3/4" ✓
Bolt pins	5/8" (sealed)	1/2" ✓
Glassholder & DL hinge pins	5/8" (sealed)	5/8" ✓
Lug thickness: glassholder	2 1" (sealed)	3/4" ✓
" " Deadlight	5/8" (sealed)	7/8" ✓

© 2020

not required abaft 1/8" L forward
provided 25% portable plugs available

0026 2/4

"Canberra"

Sidescuttles (concluded)

(D)

11" opening type above bulkhead deck

Actual

BSS

Frame & fastenings

1/2" : not given

3/8" : 11 @ 5/8" ✓

Glass thickness

1"

5/16" ✓

Glassholder bolts

2 @ 13/16"

2 @ 3/4" ✓

Deadlight & bolts

not fitted

5/16" : 1 @ 3/4" ✓

Bolt pins

5/16" (railed)

1/2" ✓

Glassholder & DL hinge pins

7/16" (railed)

5/8" ✓

Lug thickness (glassholder)

7/16" (railed)

1/16" ✓

" " (deadlight)

✓

13/16" ✓

Plug

not fitted

not required : 1/4" ✓

General Notes:-

Fastenings to shell not stated &
no particulars of materials given.

I see p 3.



© 2020

Lloyd's Register
Foundation

0026 4/4