

C. 16/14

Lloyd's Register of Shipping.

30 JUN 1943

Ship's Name "TILSINGTON COURT"

Official No. 160599

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

new Crews Accommodation, bounded by suitably stiffened steel bulkheads, has been fitted in tween decks aft, entrance from strongly constructed steel companion with hinged steel door operated both sides and having 24" sill.

Accommodation fitted with :-

W.C. and washbasins discharging above main deck and scupper discharging below main deck, all on starboard side and fitted with S.O.V.R. Valves operated from upper deck; one 8" and two 6" vents on upper deck with 36 coamings and two gooseneck vents all supplied with plug covers; strongly constructed portlights with hinged deadlights.

a tunnel escape of steel construction has been erected on upper deck aft with hinged steel door with clips operated both sides and 24" sill.

J. Dodd.

Newcastle-on-Tyne

18/6/43.

a copy of the above has been placed on board the vessel.

Noted

30 JUN 1943