

Memo

Shipbuilders: Messrs.

M.V. "Astro"

Yard No.

Engineers: Messrs.

Engine No.

Classification

It is submitted The plan showing Bilge Pumping  
Arrangement in Machinery Space has been examined and  
the arrangements as shown thereon are such as could be accepted,  
provided a direct bilge suction be led to each of the bilge pumps.  
These suction should be the same size as the suction branch on the pumps  
and should be led from opposite sides of the ~~engine room~~ machinery  
space.

It should be added for the Surveyors information that  
the three bilge suction shown on the plan are branch bilge suction  
connected to the main bilge line and not direct bilge suction as  
stated in his report.

Return plan.

Retain copy.

2500,947. T.

RHH  
5/6/57

HRS.



© 2021

Lloyd's Register  
Foundation

002682-002689-0030

SEE PREVIOUS  
DRAWINGSbase line  
thickness