

# S.S. "FORT DEE"

115'-0" x 22'-0" x 12'-9" MLD.

DRAUGHT CAT .85 D

= 10.10

Tr Spacing	21 1/2"	21"	
Item	Ship	Rule	
Kel.	7 1/2 x 1 1/8"	6 x 1 3/8"	
Garboard	.40	.34	.34
Plin shell	.35	.34	.28 + .03 + .03 = .34
Side shell	.40	.31	.28 + .03 = .31
DECK	12.6 $\square$ (each cross shell)	11.4 $\square$ "	22 x 10.83 x .048 = 11.4
Frames	4" x 3" .38 OA	3 1/2" x 2 1/2" .32 OA	NF = 1.79 (3.2 + $\frac{11 \times 8}{100}$ ) .66 x 86% = 4 @ 8'-0" long
Beams (alt pos)	5 1/2" x 3" .40 OA	6" x 3" .34 OA	N = 3.58 x .60 x 4.8 = 10.3 @ 9.75

bulme Tonnage.  $115 \times 22 \times 12.75 \times .75/100 = 242$

grade. Ci.

Rule.

2 @ 5 3/4 cwt boxes (stockless)  
1 @ 2 1/2 cwt stream  
90 fms 1" steel chain cable.

Ship  
1 Bower 5 cwt (on stock)  
1 " 4 1/2 cwt ( " )  
90 fms steel hank cable.



© 2021

Lloyd's Register  
Foundation

002682-002689-0076

S R SEAM

5' x 3' P. PINE I