

Lloyd's Register of Shipping.
SURVEYS FOR FREEBOARD.

PARTICULARS IN RESPECT OF STEAM SHIPS HAVING SPAR OR AWNING DECKS.	Port of Survey _____
	Date of Survey _____
	Name of Surveyor _____

Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.
Number in Register Book _____					
Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK Tonnage.	Moulded Depth as measured 31' 9" Main Deck. 6 F Deck
Length on LOADLINE		Frame Depth Rule "	Ceiling Sheer	Peak Tanks	" " " 39' 6" Spar or Awning Deck. 6 E Deck
CORRECTED DIMENSIONS.					
Co-efficient of fineness Any modification necessary [Para. 4 (a) to (e)*] } Co-efficient as corrected 70					NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

Allowance for strength in excess of Lloyd's rules =

State particulars—

Correction for Length:—
Length of Ship on Load Line.... 625'
Length in Table 381'
Difference..... 244'
Correction for 10ft..... 8'
× Difference ÷ 10 = 19.52'
+ 1 - 7 1/2'

Height of 'Tween Decks..... 7' 9"
(From top of beam to top of beam at side)
Correction for Height of 'Tween Decks in Spar-decked Ships.....

Freeboard Table B or C 4 - 10 3/4"
Correction for Length..... + 1 " 7 1/2"
6 - 6 1/4"

Correction for Strength in excess of Lloyd's rules.....

Correction for Iron Deck if required..... - 3 1/2"
Other Corrections (if any)..... 6 - 2 3/4"

Sheer at Stem at 1/2 length from Stem
Sternpost... " " " Sternpost...
Drop in Sheer abaft amidships.....

Round of Spar-deck Beam.....
" " Main-deck "

Length	×	Height.	State if open or closed at ends.
Forecastle	×		
Bridge.....	×		
Poop.....	×		

Winter Freeboard..... 6 - 2 3/4"
Summer Freeboard 5 - 8 1/4"
Indian Summer Freeboard.....
N. A. Winter Freeboard.....

Correction necessary because clearside amidships measured in accordance with the Statute is not taken at inter-section of the wood or steel deck with side

Winter Freeboard from Deck Line 31 - 9 1/2"
Summer " " " 31 - 9 1/2"
Indian Summer " " " 5 - 8 1/4"
N.A. Winter " " " 26 - 1 1/4"

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck:—

Fresh Water Line	above centre of Disc
Indian Summer Line	" " "
Winter Line	below " "
Winter North Atlantic Line	" " "

NOTE.—All vessels equal in strength to Lloyd's Spar-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for Ships of full scantlings to the upper deck, are to be considered as Spar-decked Ships, the freeboard for which will vary with their strength.
All vessels equal in strength to Lloyd's Awning-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for a Spar-decked Vessel, are to be considered as Awning-decked Ships, the freeboard for which will vary with their strength.
* If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.