

24.7
aft.....
29'-0" Height 7.5'

2 1/4
3 3/4
7'-11"

REPORT on the *Mass Workman Clark (1928) Ltd.*
Proposed fruit steamer No 64/29
Moulded dimensions 380' x 53' x 33'-6"

As a full scantling vessel with 50% excess sheer, normal round of beam and erections as given, the summer moulded draught is 27'-2 1/2"

As a full scantling flush deck vessel with 50% excess sheer and normal round of beam the summer moulded draught is 26'-4"

As a complete superstructure vessel having a moulded depth to 2nd deck of 25'-6", the summer moulded draught is 23'-2 1/2"

The summer moulded draught desired is 23'-9"

Hanson

© 2020
Lloyd's Register
Foundation
21/6/29

002711-002716-0062

n Tank..... LEVEL..... Half breadth.....

athing..... 2 1/2' TEAK.....

6-4
27'-2 1/2"