

40 DEC 1946

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "LOCH DEE".

Official No. 164122

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The following alterations have been carried out to entitle the vessel to the re-assignment of freeboards as an open shelter deck ship:-

- (1) D.E.M.S. accomodation within the shelter tween deck at No.5 hatch dispensed with and shell side scuttles in way removed and blanked by riveted and welded spigot plates. ✓
- (2) Tonnage openings in shelter deck restored and fitted with efficient temporary covers (wood). ✓
- (3) Closing appliances to openings in tonnage well bulkheads restored as originally fitted. ✓
- (4) Freeing ports (P & S) in tonnage well and all overboard scuppers from shelter tween deck re-opened as originally fitted. Storm valves made workable. ✓
- (5) Shelter tween deck drains to hold bilges blanked off. Drain pipes to stokehold bilges (P & S) fitted with self closing drop handle cocks at lower ends. ✓
- (6) W.T. bulkhead temporary extensions within shelter tween deck pierced P. & S. and apertures fitted with portable steel plates and hook bolts. Provision for drainage made at wings (P.&.S). ✓


A. H. Lunn

SURVEYOR TO LLOYD'S REGISTER
OF SHIPPING.

19th October, 1946.

Noted 29.
30 DEC 1946

ML-D



© 2020

Lloyd's Register
Foundation

002711-002716-0225