

Lloyd's Register of Shipping.

Ship's Name "ATHELRECENT"

Official No. 161142

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in JAN., 1932.

ADDITIONAL HATCHES ON POOP DECK.

1 port 1 starboard. to oil fuel bunker (trunked through poop)

5'2" x 2'7" x 28" coaming (.35"). watertight steel cover secured
by toggles and clips. ✓

2 port 2 starboard. to poop spacs 5'3" x 2'7" x 31" coaming (.35")
covers 3" P.P. fitted fore and aft. 3 $\frac{1}{4}$ " bearing surface. Cleats
spaced 24", battens, wedges and 2 tarpaulins. ✓

1 starboard side. to store in poop 4'2" x 3'5" x 31" coaming (.35")
covers 3" P.P. fitted fore and aft. 3 $\frac{1}{4}$ " bearing surface. Cleats
spaced 24". Battens, wedges and 2 tarpaulins. ✓

HATCH ON FORECASTLE DECK.

1 to forecastle space 4'0" x 2'6" x 24" coaming (.35")

Covers 3" P.P. fitted fore and aft. 3" bearing surface.

Cleats spaced 16", battens, wedges and 2 tarpaulins. ✓

HATCH ON FREEBOARD DECK IN FORECASTLE.

1 to fore peak space, 3'0" x 2'6" x 10" coaming (.40")

3" P.P. covers, fitted fore and aft. 3" bearing surface.

Cleats spaced 24". Bettens, wedges and 2 tarpaulins. ✓

(Liv. Jul., 1939).

BB 29/7/39.

