

Lloyd's Register of Shipping.



Port

SUNDERLAND.

29th March, 1945.

This is to Certify that

S.D. BRAND

the undersigned Surveyor to this Society did at the request of Messrs. The Sunderland Forge & Engineering Co., Ltd., attend at their Works on the 27th March, 1945, for the purpose of witnessing tests on two generating sets, Serial Nos. G.3535 and G.3537, each consisting of a 10 k.w., 110 volt, 91 amp., 850 R.P.M., continuously rated, compound wound, direct current generator coupled to a 7" x 3" enclosed type, forced lubricated steam engine suitable for a steam pressure of 100 lbs. per sq.in., the sets having been built to the order of Messrs. The Grangemouth Dockyard Co., Ltd., and intended for installation on their Yard No. 462.

A full load temperature run followed by a short run on 25% overload was witnessed on each set, followed by governing, compounding, high voltage (dielectric) and insulation resistance tests and the sets were found to be, as far as can be seen, sound and free from defects and to comply with the Society's requirements.

Copies of the Makers' certificates of tests are attached hereto.

For identification each generator was stamped on the yoke below the rating plate thus :-

LLOYD'S TEST

27.3.45.

S.D.B.

S.D. Brand

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.

YES 32 : 2 : 0.

APPLIED FOR - 3 APR 1945 © 2020

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that :-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."